



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199574

Date <u>4/30/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>35-31</u>	Lease <u>Vonder lage</u>
County <u>Weid</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #11)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>743</u>	
<u>Surface</u> <u>8 5/8" 156-24"</u>	Bottom of Surface	Ft. <u>728</u>	
Plug	Plug Landed @ <u>684</u>	Ft.	Time On <u>0505</u>
Production	Pipe Landed @ <u>728</u>	Ft.	Plug Down <u>0730</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III</u> <u>20431440RL</u>	<u>460</u>	SKS		
Poz. Mix <u>80012 090</u>				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	132	Miles		
Fuel Surcharge	132	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	<u>01658-</u>	<u>01658</u>	
Disp. Rate 5 BPM	Mixing	<u>01658-</u>	<u>0718</u>	
Slurry Vol. 1.32 ³ Cu.Ft./Sk	Change Valves	<u>0718-</u>	<u>0721</u>	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	<u>0721-</u>	<u>0730</u>	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>49°F</u>				
Total Slurry Vol. <u>108</u>	BBLS Cement			
Landed Plug @ <u>400</u>	PSI/Final Lift @ <u>100</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>43.5</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>4</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>44</u>			
<u>1214/1218</u>		Bulk Truck		<u>44/44</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Dallas - Justin

Received By Tom Bowel
Customer or His Agent