



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199606

Date <u>5/12/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>26-2</u>	Lease <u>Platte</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme "11")</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>745</u>	
<u>Surface</u>	<u>8 5/8" (56-24")</u>	Bottom of Surface	Ft. <u>722</u>
Plug	Plug Landed @ <u>678</u>	Ft.	Time On <u>0700</u>
Production	Pipe Landed @ <u>722</u>	Ft.	Plug Down <u>1000</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III 100% Excess</u>	<u>460</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % <u>Fio-Cete 1/4 # Per Sack</u>				
Mileage Charge	<u>108</u>	Miles		
Fuel Surcharge	<u>108</u>	Miles		
Additional Cement	<u>40</u>	SKS		
Mixing Rate	<u>4 BPM</u>	Pre-Flush	<u>0922-</u>	<u>0928</u>
Disp. Rate	<u>5 BPM</u>	Mixing	<u>0928-</u>	<u>0948</u>
Slurry Vol.	<u>1.32³ Cu.Ft./Sk</u>	Change Valves	<u>0948-</u>	<u>0951</u>
Slurry Wt.	<u>14.8 - 15.0 PPG</u>	Displacement	<u>0951-</u>	<u>1000</u>
Water/Cement	<u>6.25 Gal/SK</u>			
Water Temp.	<u>56° F</u>			
Total Slurry Vol.	<u>117.5</u>	BBLS Cement		
Landed Plug @	<u>325</u>	PSI/Final Lift @ <u>200</u>	PSI	
Pre-Flush W/ <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>43</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>7</u>	BBLS Cement		Total	

2651273

80012090 Del

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>36</u>			
<u>1217/1218</u>		Bulk Truck		<u>36/36</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Dallas, Justin Demaleio

Received By

Customer or His Agent