



PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 28005

LOCATION Oakley KS

FOREMAN Walt Dinkel

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY																
5-3-11	9160	Bulka State #1	20	10S	55W	Lincoln																
CUSTOMER Weeping-Fullerton			<table border="1"> <tr> <th>TRUCK #</th><th>DRIVER</th><th>TRUCK #</th><th>DRIVER</th></tr> <tr> <td>456-7718</td><td>Chad Smith</td><td></td><td></td></tr> <tr> <td>460</td><td>Cory Davis</td><td></td><td></td></tr> <tr> <td></td><td></td><td></td><td></td></tr> </table>				TRUCK #	DRIVER	TRUCK #	DRIVER	456-7718	Chad Smith			460	Cory Davis						
TRUCK #	DRIVER	TRUCK #					DRIVER															
456-7718	Chad Smith																					
460	Cory Davis																					
MAILING ADDRESS																						
CITY	STATE	ZIP CODE																				

JOB TYPE <u>Surface-0</u>	HOLE SIZE <u>12 1/4</u>	HOLE DEPTH <u>331'</u>	CASING SIZE & WEIGHT <u>8 5/8 - 23#</u>
CASING DEPTH <u>331'</u>	DRILL PIPE _____	TUBING _____	OTHER _____
SLURRY WEIGHT <u>15.2</u>	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>20'</u>
DISPLACEMENT <u>19 3/4</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE <u>5 BPM</u>

REMARKS: Safety Meeting, Rig up to cive
mixed 250 sks com, 3% cc - 2% cel, 1/4# Flo-Sol
Displaced 1934 BBL H₂O, Shut in

Cement D/D Circ.
Approx 5 BBL to Pit

Thank You
Wally Crew

[illegible]

Rayin 3737

SALES TAX	336.31
ESTIMATED TOTAL	7522.70
DATE	5/3/11

AUTHORIZATION Dean Smith TITLE Co Rep

DATE 5/3/11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER **30765**
LOCATION Oakley
FOREMAN Kelly Gabe
Walt Dunkel

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5-16-11	9160	Bubba state #1	20	10S	55W	Lincoln
CUSTOMER <u>Weipking - Fullerton</u>						
MAILING ADDRESS						
CITY						
STATE						
ZIP CODE						
			TRUCK #	DRIVER	TRUCK #	DRIVER
			399	Tim W.		
			460	Damen White		

JOB TYPE Prod HOLE SIZE 7 7/8 HOLE DEPTH 7789 CASING SIZE & WEIGHT 5 1/2 17#
CASING DEPTH 7280 DRILL PIPE _____ TUBING _____ OTHER PC 7536
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 43'
DISPLACEMENT 168 DISPLACEMENT PSI _____ MIX PSI _____ RATE 7 BPM

REMARKS: Safety Meeting, Run float equipment centralizers on STS
1,2,3,4,5 centralizers on 165 & 166, Baskets on 166 Port collar on 165
Run 100 STS circ. run casing to bottom circ. 1 hr

mixed 10 sks in M.H., 10 sks in R.H., Pump 10 BBL H₂O, 50 gal mud Flush, 10 BBL
H₂O, mixed 140 sks "H", 10% salt, 5# Kalseal, 2% Col, Clear Pump + Lines
release Plug + Displace 165 BBL H₂O @ 1200# max, Landed Plug @ 1800#
release Pressure, Float Held

Thank You
Kelly + Crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401P	1	PUMP CHARGE	4050 ⁰⁰	4050 ⁰⁰
5406	100	MILEAGE	5 ⁰⁰	500 ⁰⁰
1115A	160 sks	Class H Cement	22 ⁰⁰	3,520 ⁰⁰
1111	757 #	Salt	142	31794
1110A	800 #	Kalseal	153	424 ⁰⁰
1118B	300 #	Bentonite	24	72 ⁰⁰
1144G	500 gal	mud Flush	1 ⁰⁰	500 ⁰⁰
5407A	7.52	Ton Mileage Delivery	158	1,188 ¹⁶
4159	1	AFU Float shoe	413 ⁰⁰	413 ⁰⁰
4454	1	Latch down Plug assy	303 ⁰⁰	303 ⁰⁰
4136	5	Turbo-Centralizers	72 ⁰⁰	360 ⁰⁰
4130	2	Centralizers	58 ⁰⁰	116 ⁰⁰
4104	2	Baskets	276 ⁰⁰	552 ⁰⁰
4285	1	Port Collar	2,075 ⁰⁰	2,075 ⁰⁰
				14,391 ¹⁰
				- 2,158 ⁶⁰
				12,232 ⁴⁰
			SALES TAX	573 ⁸⁹
			ESTIMATED	
			TOTAL	72,806 ¹¹

Ravin 3737

AUTHORIZATION Danny Smith

TITLE Co-man

DATE 5/17/11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



FIELD TICKET & TREATMENT REPORT CEMENT

TICKET NUMBER 28023

LOCATION Oakley Is

FOREMAN Walt Dinkel

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
5-31-11	960	Bubba State #1	20	10S	55W	Lincoln
CUSTOMER Weirking Fullerton						
MAILING ADDRESS						
CITY		STATE	ZIP CODE			

JOB TYPE <u>Port Callar</u>	HOLE SIZE _____	HOLE DEPTH _____	CASING SIZE & WEIGHT <u>5 1/2 - 17"</u>
CASING DEPTH _____	DRILL PIPE _____	TUBING <u>2 7/8 - 4535'</u>	OTHER <u>PC - 4535'</u>
SLURRY WEIGHT _____	SLURRY VOL _____	WATER gal/sk _____	CEMENT LEFT in CASING <u>4533</u>
DISPLACEMENT <u>26 1/4 Bbl</u>	DISPLACEMENT PSI _____	MIX PSI _____	RATE <u>1 BPM</u>

REMARKS: Safety Meeting, Rig up to well Test casing to 1500# Held
mixed 200 sks 8940pm, 6% Gel, 5# Kd seal, 2% cc, 1/4" Flo-Seal
During last 30-40 sks Rubber blow out Displaced 25 BBL, shot Tool
Tried to Reverse out, Rubber began leaking bad, replaced Rubber,
Hook up to Tubing, Tried to move cement, Pressured to 4000#
Pull Tubing,

Thank You
Walt & crew

[illegible]

Rayin 3737

AUTHORIZTION

TITLE

DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.