



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7289 • FAX (970) 353-7712

OUR INVOICE

199520

Date <u>3/2/2011</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>34-36</u>	Lease <u>PADDLE</u>
County <u>WELD</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (XTREME #12)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Ft. <u>936</u>	
<u>Surface</u> <u>8 7/8" CSG 24"</u>	Bottom of Surface	Ft. <u>926</u>	
Plug	Plug Landed @ <u>892</u>	Ft. <u>Time On 2000</u>	
Production	Pipe Landed @ <u>926</u>	Ft. <u>Plug Down 2215</u>	

Description	Qty	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>TYPE III</u>	<u>590</u>	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cote 1/4 # Per Sack				
Mileage Charge	<u>264</u>	Miles		
Fuel Surcharge	<u>264</u>	mtics		
Additional Cement		SKS		
Mixing Rate <u>4 BPM</u>	Pre-Flush	<u>2136</u>	<u>2136</u>	
Disp. Rate <u>5 BPM</u>	Mixing	<u>2136</u>	<u>2241</u>	
Slurry Vol. <u>1.32 Cu.Ft./Sk</u>	Change Valves	<u>2201</u>	<u>2204</u>	
Slurry Wt. <u>14.8 - 15.0 PPG</u>	Displacement	<u>2204</u>	<u>2215</u>	
Water/Cement <u>6.25 Gal/SK</u>				
Water Temp.				
Total Slurry Vol. <u>136.3</u>	BBLs Cement			
Landed Plug @ <u>430</u>	PSI/Final Lift @ <u>150</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>55.5</u>	BBLs H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>4</u>	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>88</u>			
<u>1214/1218</u>		Bulk Truck		<u>88/88</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/ADAM/STEVE/DSCAR

Received By [Signature]

Customer or His Agent