



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 199584

Date	5-4-11	Well Owner	Kerr McGee	Well No.	37-4	Lessee	SPIVEY
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	652		
Surface	8 5/8" CSC-24 H	Bottom of Surface		Ft.	637		
Plug		Plug Landed @	593	Ft.	Time On	0030	
Production		Ripe Landed @	637	Ft.	Plug Down	0400	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III 2043342 DRL	400	SKS		
Poz. Mix				
Calcium Chloride 800 12 090	2.5	%		
Gel % Fip-Cete 1/4 # Per Sack				
Mileage Charge	60	Miles		
Fuel Surcharge	60	MILES		
Additional Cement TOP JOB	60	SKS		
Mixing Rate 4 BPM	Pre-Flush	0317	-0322	
Disp. Rate 5 BPM	Mixing	0322	-0349	
Slurry Vol. 1.32 <sup>3</sup> Cu.Ft./SK	Change Valves	0349	-0352	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0352	-0400	
Water/Cement 6.25 Gal/SK				
Water Temp. 46° F				
Total Slurry Vol. 108.1	BBLS Cement			
Landed Plug @ 300	PSI/Final Lift @ 280	PSI		
Pre-Flush W/ 20	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace W/ 37.7	BBLS H <sub>2</sub> O	State CO 2.9%	Tax	
Circulate 5	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		30			
1214		Bulk Truck		30			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, KERRY, EVAN

Received By Tom Bowser  
Customer or His Agent