


FORM 2 Rev 12/05	State of Colorado Oil and Gas Conservation Commission 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table>	DE	ET	OE	ES
DE	ET	OE	ES				
APPLICATION FOR PERMIT TO:			Document Number: 400179530 Plugging Bond Surety 20100017				
1. <input checked="" type="checkbox"/> Drill, <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> COALBED <input type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/> COMMINGLE ZONE <input checked="" type="checkbox"/>			Refiling <input type="checkbox"/> Sidetrack <input type="checkbox"/>				
3. Name of Operator: <u>ENCANA OIL & GAS (USA) INC</u>		4. COGCC Operator Number: <u>100185</u>					
5. Address: <u>370 17TH ST STE 1700</u> City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202-5632</u>							
6. Contact Name: <u>Nick Curran</u> Phone: <u>(720)876-5288</u> Fax: <u>(720)876-6288</u> Email: <u>nick.curran@encana.com</u>							
7. Well Name: <u>Anderson</u>		Well Number: <u>22-32</u>					
8. Unit Name (if appl): _____		Unit Number: _____					
9. Proposed Total Measured Depth: <u>8344</u>							
WELL LOCATION INFORMATION							
10. QtrQtr: <u>NENW</u> Sec: <u>32</u> Twp: <u>2N</u> Rng: <u>68W</u> Meridian: <u>6</u> Latitude: <u>40.100950</u> Longitude: <u>-105.029770</u>							
Footage at Surface: <u>510</u> feet FNL/FSL <u>FNL</u> <u>1985</u> feet FEL/FWL <u>FWL</u>							
11. Field Name: <u>WATTENBERG</u>		Field Number: <u>90750</u>					
12. Ground Elevation: <u>4937</u>		13. County: <u>WELD</u>					
14. GPS Data: Date of Measurement: <u>11/19/2010</u> PDOP Reading: <u>1.2</u> Instrument Operator's Name: <u>Craig Burke</u>							
15. If well is <input checked="" type="checkbox"/> Directional <input type="checkbox"/> Horizontal (highly deviated) submit deviated drilling plan. Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL <u>2130</u> <u>FNL</u> <u>1980</u> <u>FWL</u> <u>2130</u> <u>FNL</u> <u>1980</u> <u>FWL</u> Sec: <u>32</u> Twp: <u>2N</u> Rng: <u>68W</u> Sec: <u>32</u> Twp: <u>2N</u> Rng: <u>68W</u>							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>314 ft</u>							
18. Distance to nearest property line: <u>650 ft</u> 19. Distance to nearest well permitted/completed in the same formation: <u>708 ft</u>							
20. LEASE, SPACING AND POOLING INFORMATION							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)			
Codell	CODL	407	320	N/2			
J Sand	JSND	232	320	N2			
Niobrara	NBRR	407	320	N/2			

IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):
T2NR68W SEC 32 E2NW4, NE4

25. Distance to Nearest Mineral Lease Line: _____ 505 ft _____ 26. Total Acres in Lease: _____ 240 _____

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☒ Yes ☐ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: CLOSE LOOP SYS WILL BE

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	800	291	800	
1ST	7+7/8	4+1/2	11.6	0	8,344	172	8,344	7,270
			Stage Tool		5,353	732	5,353	4,299

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments No open hole logs will be ran. No conductor casing will be used. Stage Tool (200' below Shn to 200' above Sx)

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Nick CUrnan

Title: Permitting Agent Date: 6/28/2011 Email: Nick.Curran@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/24/2011

API NUMBER

05 123 34037 00

Permit Number: _____ Expiration Date: 7/23/2013

CONDITIONS OF APPROVAL, IF ANY: _____

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
400179530	FORM 2 SUBMITTED
400179911	WELL LOCATION PLAT
400179912	EXCEPTION LOC REQUEST
400179913	WAIVERS
400179914	LEASE MAP
400179915	SURFACE AGRMT/SURETY
400179916	DEVIATED DRILLING PLAN
400179917	NRCS MAP UNIT DESC
400179918	30 DAY NOTICE LETTER
400179920	TOPO MAP

Total Attach: 10 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)