


<b>FORM</b> <b>2</b> Rev 12/05	<b>State of Colorado</b> <b>Oil and Gas Conservation Commission</b> 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table>	DE	ET	OE	ES
DE	ET	OE	ES				
<b>APPLICATION FOR PERMIT TO:</b>			Document Number:  400182099  Plugging Bond Surety  20010124				
1. <input checked="" type="checkbox"/> <b>Drill,</b> <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> COALBED <input type="checkbox"/> OTHER _____ SINGLE ZONE <input checked="" type="checkbox"/> MULTIPLE ZONE <input type="checkbox"/> COMMINGLE ZONE <input type="checkbox"/>		Refiling <input type="checkbox"/> Sidetrack <input type="checkbox"/>					
3. Name of Operator: <u>KERR-MCGEE OIL &amp; GAS ONSHORE LP</u> 4. COGCC Operator Number: <u>47120</u>							
5. Address: <u>P O BOX 173779</u> City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80217-3779</u>							
6. Contact Name: <u>REBECCA HEIM</u> Phone: <u>(720)929-6361</u> Fax: <u>(720)929-7361</u> Email: <u>rebecca.heim@anadarko.com</u>							
7. Well Name: <u>HOWARD</u> Well Number: <u>9C-29HZ</u>							
8. Unit Name (if appl): _____    Unit Number: _____							
9. Proposed Total Measured Depth: <u>12423</u>							
<b>WELL LOCATION INFORMATION</b>							
10. QtrQtr: <u>SWNE</u> Sec: <u>32</u> Twp: <u>1N</u> Rng: <u>67W</u> Meridian: <u>6</u> Latitude: <u>40.007998</u> Longitude: <u>-104.910214</u>							
Footage at Surface: <u>2491</u> feet    FNL/FSL <u>FNL</u> 1501 feet    FEL/FWL <u>FEL</u>							
11. Field Name: <u>WATTENBERG</u> Field Number: <u>90750</u>							
12. Ground Elevation: <u>5057</u> 13. County: <u>WELD</u>							
14. GPS Data: Date of Measurement: <u>03/17/2011</u> PDOP Reading: <u>2.2</u> Instrument Operator's Name: <u>OWEN McKEE</u>							
15. If well is <input type="checkbox"/> Directional <input checked="" type="checkbox"/> Horizontal (highly deviated) <b>submit deviated drilling plan.</b> Footage at Top of Prod Zone:    FNL/FSL    FEL/FWL    Bottom Hole:    FNL/FSL    FEL/FWL <u>2006</u> <u>FNL</u> <u>526</u> <u>FEL</u> <u>2180</u> <u>FSL</u> <u>510</u> <u>FEL</u> Sec: <u>29</u> Twp: <u>1N</u> Rng: <u>67W</u> Sec: <u>29</u> Twp: <u>1N</u> Rng: <u>67W</u>							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>306 ft</u>							
18. Distance to nearest property line: <u>151 ft</u> 19. Distance to nearest well permitted/completed in the same formation: <u>1531 ft</u>							
<b>20. LEASE, SPACING AND POOLING INFORMATION</b>							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)			
Codell	CODL		160	GWA			

**IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.**

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☐ No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
SEE ATTACHED OIL AND GAS LEASE

25. Distance to Nearest Mineral Lease Line: 510 ft 26. Total Acres in Lease: 5753

**DRILLING PLANS AND PROCEDURES**

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: \_\_\_\_\_

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

If 28, 29, or 30 are "Yes" a pit permit may be required.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,100	360	1,100	0
1ST	8+3/4	7+0/0	26	0	8,237	760	8,237	
2ND	6+1/8	4+1/2	11.6	7225	12,423			

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be used. Operator requests approval of a Rule 318Aa, Rule 318Ae, and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window, the well will be drilled to a 318Ae infill location from outside of a GWA drilling window, and the wellhead will be located more than 50' from an existing well location. Unit Configuration: Sec 29 E/2SE/4; Sec 32 E/2NE/4

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: REBECCA HEIM

Title: REGULATORY ANALYST II Date: 7/6/2011 Email: DJREGULATORY@ANADARK

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 7/27/2011

Permit Number: \_\_\_\_\_ Expiration Date: 7/26/2013

**API NUMBER**

05 123 34047 00

**CONDITIONS OF APPROVAL, IF ANY:**

**All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.**

Wellhead is to be located outside of a GWA drilling window, the well will be drilled to a 318Ae infill location from a surface location outside of a GWA drilling window, and the wellhead will be located more than 50' from an existing well location. EXCEPTION GRANTED.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from end of 7" production casing to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

**Attachment Check List**

Att Doc Num	Name
1771335	SURFACE CASING CHECK
400182099	FORM 2 SUBMITTED
400182109	30 DAY NOTICE LETTER
400182112	DEVIATED DRILLING PLAN
400182113	PLAT
400182115	TOPO MAP
400182117	OIL & GAS LEASE
400182118	OIL & GAS LEASE
400182119	WAIVERS
400182120	EXCEPTION LOC REQUEST
400182123	PROPOSED SPACING UNIT

Total Attach: 11 Files

**General Comments**

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Operator requests approval of a Rule 318Aa, Rule 318Ae, and Rule 318Ac exception location: Wellhead is to be located outside of a GWA drilling window, the well will be drilled to a 318Ae infill location from outside of a GWA drilling window, and the wellhead will be located more than 50' from an existing well location.	7/11/2011 12:51:43 PM

Total: 1 comment(s)

**BMP**

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)