


<b>FORM</b> <b>2</b> Rev 12/05	<b>State of Colorado</b> <b>Oil and Gas Conservation Commission</b> 1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109		<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 25%;">DE</td> <td style="width: 25%;">ET</td> <td style="width: 25%;">OE</td> <td style="width: 25%;">ES</td> </tr> </table>	DE	ET	OE	ES
DE	ET	OE	ES				
<b>APPLICATION FOR PERMIT TO:</b>			Document Number:  400161769  Plugging Bond Surety  20030009				
1. <input checked="" type="checkbox"/> <b>Drill,</b> <input type="checkbox"/> Deepen, <input type="checkbox"/> Re-enter, <input type="checkbox"/> Recomplete and Operate							
2. TYPE OF WELL OIL <input type="checkbox"/> GAS <input checked="" type="checkbox"/> COALBED <input type="checkbox"/> OTHER _____ SINGLE ZONE <input type="checkbox"/> MULTIPLE ZONE <input checked="" type="checkbox"/> COMMINGLE ZONE <input type="checkbox"/>		Refiling <input type="checkbox"/> Sidetrack <input type="checkbox"/>					
3. Name of Operator: <u>NOBLE ENERGY INC</u>		4. COGCC Operator Number: <u>100322</u>					
5. Address: <u>1625 BROADWAY STE 2200</u> City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80202</u>							
6. Contact Name: <u>SUSAN MILLER</u> Phone: <u>(303)228-4246</u> Fax: <u>(303)228-4286</u> Email: <u>smiller@nobleenergyinc.com</u>							
7. Well Name: <u>STEWARDSON USX</u>		Well Number: <u>WW33-01D</u>					
8. Unit Name (if appl): _____		Unit Number: _____					
9. Proposed Total Measured Depth: <u>8454</u>							
<b>WELL LOCATION INFORMATION</b>							
10. QtrQtr: <u>NWNE</u> Sec: <u>33</u> Twp: <u>1N</u> Rng: <u>66W</u> Meridian: <u>6</u> Latitude: <u>40.013160</u> Longitude: <u>-104.780270</u>							
Footage at Surface: <u>652</u> feet    FNL/FSL <u>FNL</u> <u>2121</u> feet    FEL/FWL <u>FEL</u>							
11. Field Name: <u>Wattenberg</u>		Field Number: <u>90750</u>					
12. Ground Elevation: <u>5072</u>		13. County: <u>WELD</u>					
14. GPS Data: Date of Measurement: <u>03/14/2011</u> PDOP Reading: <u>1.2</u> Instrument Operator's Name: <u>Robert Daley</u>							
15. If well is <input checked="" type="checkbox"/> Directional <input type="checkbox"/> Horizontal (highly deviated) <b>submit deviated drilling plan.</b> Footage at Top of Prod Zone:    FNL/FSL    FEL/FWL    Bottom Hole:    FNL/FSL    FEL/FWL <u>660</u> <u>FNL</u> <u>660</u> <u>FEL</u> <u>660</u> <u>FNL</u> <u>660</u> <u>FEL</u> Sec: <u>33</u> Twp: <u>1N</u> Rng: <u>66W</u> Sec: <u>33</u> Twp: <u>1N</u> Rng: <u>66W</u>							
16. Is location in a high density area? (Rule 603b)? <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No							
17. Distance to the nearest building, public road, above ground utility or railroad: <u>638 ft</u>							
18. Distance to nearest property line: <u>622 ft</u> 19. Distance to nearest well permitted/completed in the same formation: <u>1511 ft</u>							
<b>20. LEASE, SPACING AND POOLING INFORMATION</b>							
Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)			
Codell	CODL	407-87	80	N/2NE/4			
J Sand	JSND	232-23	320	N/2			
Niobrara	NBRR	407-87	80	N/2NE/4			

**IMPORTANT: SOME DATA FIELDS HAVE BEEN MODIFIED.**

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: \_\_\_\_\_

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20030012

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):  
T1N, R66W, SECTION 33: ALL

25. Distance to Nearest Mineral Lease Line: 660 ft 26. Total Acres in Lease: 640

**DRILLING PLANS AND PROCEDURES**

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

Method: ☒ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: CLOSED LOOP

If 28, 29, or 30 are "Yes" a pit permit may be required.

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	1,360	560	1,360	0
1ST	7+7/8	4+1/2	11.6	0	8,454	836	8,454	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☐ Rotating Head ☐ None

33. Comments Conductor casing will not be used. First string top of cement will be 200' above the Niobrara formation. This is part of a 7 well pad which includes: proposed Stewardson USX WW33-01D, WW33-03D, Vista USX WW33-06D, WW33-07D, WW33-08D, WW33-17D and twinning existing Stewardson 31-33 (as-built GPS sundry notice submitted for straight hole well). See form 2A doc. no. 400161795 which covers all 7 wells.

34. Location ID: 332438

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: SUSAN MILLER

Title: Regulatory Analyst II Date: 7/7/2011 Email: smiller@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin Director of COGCC Date: 7/28/2011

**API NUMBER**

05 123 34068 00

Permit Number: \_\_\_\_\_ Expiration Date: 7/27/2013

**CONDITIONS OF APPROVAL, IF ANY:**

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

### **Attachment Check List**

Att Doc Num	Name
400161769	FORM 2 SUBMITTED
400161794	30 DAY NOTICE LETTER
400179941	WELL LOCATION PLAT
400179942	DEVIATED DRILLING PLAN

Total Attach: 4 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Changed BHL from 660 FNL & 2121 FEL to 660 FNL & 660 FEL per well plat.	7/12/2011 1:03:26 PM

Total: 1 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) and General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location and will remain in place until the pad reaches final reclamation.
General Housekeeping	General housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur, prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pick up trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.

Total: 3 comment(s)