



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199554

Date <u>4/17/2011</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>37-9</u>	Lease <u>THOMASON</u>				
County <u>WELD</u>	State <u>Colorado</u>						
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>							
Address <u>1999 Broadway, Suite 3700</u>	<u>(PATTERSON # 159)</u>						
City, State Zip <u>Denver, Colorado 80202</u>							
Type of Job <u>Surface</u>	Depth <u>800</u>	Fl. <u>793</u>					
<u>8 5/8 CSG 24"</u>	Bottom of Surface	Fl. <u>793</u>					
Plug	Plug Landed @ <u>749</u>	Fl. <u>749</u>	Time On <u>0630</u>				
Production	Pipe Landed @ <u>743</u>	Fl. <u>743</u>	Plug Down <u>0920</u>				
Description	Qty.	Meas.	Unit Price Amount				
Set Up Charge	1						
Cement Nest <u>TYPE III</u>	500	SKS					
Poz. Mix							
Calcium Chloride	2.5	%					
Gel % Flo-Crete 1/4 # Per Sack							
Mileage Charge	156	Miles					
Fuel Surcharge	156	MILES					
Additional Cement		SKS					
Mixing Rate	4 BPM	Pre-Flush	0839	0845			
Disp. Rate	5 BPM	Mixing	0845	0907			
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0907	0910			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0910	0920			
Water/Cement	6.25 Gal/SK						
Water Temp.	46						
Total Slurry Vol.	117.5	BBLS Cement					
Landed Plug @	430	PSI/Final Lift @	400	PSI			
Pre-Flush W/	30	BBLS H ₂ O	Tax Reference Code	Sub Total			
Displace W/	47.5	BBLS H ₂ O	State	CO 2.9%			
Circulate	3	BBLS Cement	Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		52			
1216/1215		Bulk Truck		52/52			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/ADAM/STEVE

Received By [Signature]
Customer or His Agent