



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199545

Date <u>4/21/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>110-9</u>	Lease <u>Thomason</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Patterson #189)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	FL	<u>780</u>
<u>Surface</u>	<u>8 5/8" CSG-24"</u>	Bottom of Surface	FL <u>768</u>
Plug	Plug Landed @ <u>724</u>	FL	Time On <u>0545</u>
Production	Pipe Landed @ <u>768</u>	FL	Plug Down <u>0900</u>

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III</u>	480	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % <u>Fio-Cete 1/4 # Per Sack</u>	<u>2047813</u>			
Mileage Charge	<u>80017090</u>	156	Miles	
Fuel Surcharge		156	Miles	
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0821-	0827
Disp. Rate	5 BPM	Mixing	0827-	0848
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0848-	0851
Slurry WL	14.8 - 15.0 PPG	Displacement	0851-	0900
Water/Cement	6.25 Gal/SK			
Water Temp.	<u>55°F</u>			
Total Slurry Vol.	<u>113</u>	BBLs Cement		
Landed Plug @	<u>385</u>	PSI/Final Lift @ <u>200</u>	PSI	
Pre-Flush W/	<u>30</u>	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	<u>46</u>	BBLs H ₂ O	State <u>CO 2.9%</u>	Tax
Circulate	<u>5</u>	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>52</u>			
<u>1207/1217</u>		Bulk Truck		<u>52/52</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Dallas, Justin & Oscar

Received By W.D. Hall

Customer or His Agent