



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7289 • FAX (970) 353-7712

OUR INVOICE

199541

Date <u>4/24/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>39-9</u>	Lease <u>THOMASON</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Patterson #189)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>785</u>	
<u>Surface</u>	<u>8 5/8" 15G-24"</u>	Bottom of Surface	Fl. <u>771</u>
Plug	Plug Landed @ <u>727</u>	Fl. Time On <u>1005</u>	
Production	Pipe Landed @ <u>771</u>	Fl. Plug Down <u>1200</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III</u>	490	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % <u>Fio-Ceto 1/4 # Per Sack</u>	<u>204-7875</u>			
Mileage Charge	<u>20012090</u>	156	Miles	
Fuel Surcharge	156	Miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1121-	1127
Disp. Rate	5 BPM	Mixing	1127-	1148
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	1148-	1151
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1151-	1200
Water/Cement	6.25 Gal/SK			
Water Temp.	<u>59°F</u>			
Total Slurry Vol.	<u>115</u>	BBLS Cement		
Landed Plug @	<u>325</u>	PSI/Final Lift @ <u>100</u>	PSI	
Pre-Flush W/	<u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	<u>46</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax
Circulate	<u>5</u>	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>52</u>			
<u>1214/1218</u>		Bulk Truck		<u>52/52</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Dallas, Justin, Oscar

Received By M. T. Hill

Customer or His Agent