

FORM  
5

Rev  
02/08

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400184987

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type  Final completion  Preliminary completion

1. OGCC Operator Number: 47120  
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP  
3. Address: P O BOX 173779  
City: DENVER State: CO Zip: 80217-  
4. Contact Name: Cindy Vue  
Phone: (720) 929-6832  
Fax: (720) 929-7832

5. API Number 05-123-29218-00  
6. County: WELD  
7. Well Name: BADDING Well Number: 39-26  
8. Location: QtrQtr: NESE Section: 26 Township: 2N Range: 66W Meridian: 6  
Footage at surface: Distance: 1320 feet Direction: FSL Distance: 1260 feet Direction: FEL  
As Drilled Latitude: 40.105664 As Drilled Longitude: -104.739398

GPS Data:  
Date of Measurement: 06/09/2011 PDOP Reading: 2.6 GPS Instrument Operator's Name: Renee Doiron

\*\* If directional footage at Top of Prod. Zone Dist.: 1299 feet. Direction: FSL Dist.: 41 feet. Direction: FEL  
Sec: 26 Twp: 2N Rng: 66W  
\*\* If directional footage at Bottom Hole Dist.: 1311 feet. Direction: FSL Dist.: 40 feet. Direction: FEL  
Sec: 26 Twp: 2N Rng: 66W

9. Field Name: WATTENBERG 10. Field Number: 90750  
11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 04/13/2011 13. Date TD: 04/16/2011 14. Date Casing Set or D&A: 04/17/2011

15. Well Classification:  
 Dry  Oil  Gas/Coalbed  Disposal  Stratigraphic  Enhanced Recovery  Storage  Observation

16. Total Depth MD 8296 TVD\*\* 8140 17 Plug Back Total Depth MD 8246 TVD\*\* 8090

18. Elevations GR 5087 KB 5102  
One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:  
PRELIMINARY FORM 5  
OPEN HOLE LOGS BRIDGED OUT AT 1217', W/O CBL TO PICK PERFORATIONS.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	1,128	710	0	1,128	CALC
1ST	7+7/8	4+1/2	11.6#	0	8,282	240	5,818	8,282	CALC

ADDITIONAL CEMENT

Cement work date: 04/17/2011

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	5,818	670	1,027	5,818

21. Formation log intervals and test zones:

<b>FORMATION LOG INTERVALS AND TEST ZONES</b>					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
J SAND	8,131		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: 7/14/2011 Email: Cindy.Vue@anadarko.com

### Attachment Check List

Att Doc Num	Document Name	attached ?	
<b>Attachment Checklist</b>			
400185004	CMT Summary *	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
400185003	Directional Survey **	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Logs	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
	Other	Yes <input type="checkbox"/>	No <input checked="" type="checkbox"/>
<b>Other Attachments</b>			
400184987	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/>	No <input type="checkbox"/>

### General Comments

User Group	Comment	Comment Date
Engineer	Preliminary Form 5, no CBL yet.	3/4/2011 2:19:11 PM
Permit	ATTACHED D.S. OKAY; HAVE LAS CBL, STILL NEED PAPER CBL.	3/2/2011 3:38:11 PM

Total: 2 comment(s)