

FORM
5A

Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400190669

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120

4. Contact Name: Cindy Vue

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6832

3. Address: P O BOX 173779

Fax: (720) 929-7832

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-33015-00

6. County: WELD

7. Well Name: THOMASON

Well Number: 4-15

8. Location: QtrQtr: NWNW Section: 15 Township: 2N Range: 65W Meridian: 6

9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA-CODELL

Status: PRODUCING

Treatment Date: 06/30/2011

Date of First Production this formation: 07/11/2011

Perforations Top: 7026 Bottom: 7276 No. Holes: 126 Hole size: 0.44

Provide a brief summary of the formation treatment:

Open Hole: ☐

NB PERF 7026-7166 HOLES 62 SIZE 0.43 CD PERF 7260-7276 HOLES 64 SIZE 0.44
Frac Niobrara B & C down 4-1/2" Csg w/ 252 gal 15% HCl & 234,360 gal Slickwater w/ 45,200# 40/70, 4,000# SB Excel
Frac Codell down 4-1/2" Csg w/ 207,018 gal Slickwater w/ 38,500# 40/70, 4,000# SB Excel

This formation is commingled with another formation: ☐ Yes ☒ No

Test Information:

Date: 07/12/2011 Hours: 24 Bbls oil: 20 Mcf Gas: 125 Bbls H2O: 0

Calculated 24 hour rate: Bbls oil: 20 Mcf Gas: 125 Bbls H2O: 0 GOR: 6250

Test Method: FLOWING Casing PSI: 1779 Tubing PSI: Choke Size: 14/64

Gas Disposition: SOLD Gas Type: WET BTU Gas: 1246 API Gravity Oil: 49

Tubing Size: Tubing Setting Depth: Tbg setting date: Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt

Bridge Plug Depth: Sacks cement on top:

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Cindy Vue

Title: Regulatory Analyst II Date: 7/29/2011 Email: Cindy.Vue@anadarko.com

Attachment Check List

Att Doc Num	Name
400190669	FORM 5A SUBMITTED

Total Attach: 1 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
-------------------	----------------	---------------------

--	--	--

Total: 0 comment(s)