

FORM
5A
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

COMPLETED INTERVAL REPORT

Document Number:
400185767

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: <u>47120</u>	4. Contact Name: <u>CARA MAHLER</u>
2. Name of Operator: <u>KERR-MCGEE OIL & GAS ONSHORE LP</u>	Phone: <u>(720) 929-6029</u>
3. Address: <u>P O BOX 173779</u>	Fax: <u>(720) 929-7029</u>
City: <u>DENVER</u> State: <u>CO</u> Zip: <u>80217-</u>	

5. API Number <u>05-123-20891-00</u>	6. County: <u>WELD</u>
7. Well Name: <u>SARCHET</u>	Well Number: <u>8-23A</u>
8. Location: QtrQtr: <u>SENE</u> Section: <u>23</u> Township: <u>3N</u> Range: <u>66W</u> Meridian: <u>6</u>	
9. Field Name: _____	Field Code: _____

Completed Interval

FORMATION: GREENHORN Status: TEMPORARILY ABANDONED

Treatment Date: 06/07/2011 Date of First Production this formation: _____
Perforations Top: 7630 Bottom: 7675 No. Holes: 90 Hole size: 0.38

Provide a brief summary of the formation treatment: _____ Open Hole:

SAND PLUG SET @ 7780

This formation is commingled with another formation: Yes No

Test Information:

Date: _____ Hours: _____ Bbls oil: _____ Mcf Gas: _____ Bbls H2O: _____
Calculated 24 hour rate: _____ Bbls oil: _____ Mcf Gas: _____ Bbls H2O: _____ GOR: _____
Test Method: _____ Casing PSI: _____ Tubing PSI: _____ Choke Size: _____
Gas Disposition: _____ Gas Type: _____ BTU Gas: _____ API Gravity Oil: _____
Tubing Size: _____ Tubing Setting Depth: _____ Tbg setting date: _____ Packer Depth: _____

Reason for Non-Production:

SAND PLUG SET @ 7780

Date formation Abandoned: 06/07/2011 Squeeze: Yes No If yes, number of sacks cmt _____

Bridge Plug Depth: 7780 Sacks cement on top: _____

FORMATION: NIOBRARA-CODELL Status: PRODUCING

Treatment Date: 06/30/2011 Date of First Production this formation: 07/06/2011
Perforations Top: 7177 Bottom: 7416 No. Holes: 122 Hole size: 0.42

Provide a brief summary of the formation treatment: _____ Open Hole:

NB PERF: 7177-7260 HOLES 66 SIZE .42 CD PERF: 7402-7416 HOLES 56 SIZE .38
Frac Niobrara A & B & C down 4-1/2" Csg w/ 250 gal 15% HCl & 243,037 gal Slickwater w/ 201,560# 40/70, 4,000# SB Excel.
Frac Codell down 4-1/2" Csg w/ 194,813 gal Slickwater w/ 150,720# 40/70, 4,180# SB Excel.

This formation is commingled with another formation: Yes No

Test Information:

Date: 08/08/2011 Hours: 24 Bbls oil: 19 Mcf Gas: 181 Bbls H2O: 0
Calculated 24 hour rate: _____ Bbls oil: 19 Mcf Gas: 181 Bbls H2O: 0 GOR: 9526
Test Method: FLOWING Casing PSI: 707 Tubing PSI: 459 Choke Size: 24/64
Gas Disposition: SOLD Gas Type: WET BTU Gas: 1230 API Gravity Oil: 59
Tubing Size: 2 + 3/8 Tubing Setting Depth: 7357 Tbg setting date: 07/12/2011 Packer Depth: _____

Reason for Non-Production:

Date formation Abandoned: _____ Squeeze: Yes No If yes, number of sacks cmt _____

Bridge Plug Depth: _____ Sacks cement on top: _____

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: CARA MAHLER

Title: REGULATORY ANALYST 1 Date: _____ CARA.MAHLER@ANADARKO.COM

Email
:

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)