

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER _____
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refiling ☐
Sidetrack ☐

Document Number:

400157786

PluggingBond SuretyID

20010124

3. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

4. COGCC Operator Number: 47120

5. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-3779

6. Contact Name: REBECCA HEIM Phone: (720)929-6361 Fax: (720)929-7361

Email: rebecca.heim@anadarko.com

7. Well Name: RIVERBEND Well Number: 3-13

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 8339

WELL LOCATION INFORMATION

10. QtrQtr: NWNW Sec: 13 Twp: 1N Rng: 67W Meridian: 6

Latitude: 40.055934 Longitude: -104.847381

Footage at Surface: 865 feet FNL 320 feet FWL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4952 13. County: WELD

14. GPS Data:

Date of Measurement: 04/27/2010 PDOP Reading: 1.9 Instrument Operator's Name: CHRIS PEARSON

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: 660 FNL 1980 FWL 660 FNL 1980 FWL
Sec: 13 Twp: 1N Rng: 67W Sec: 13 Twp: 1N Rng: 67W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 225 ft

18. Distance to nearest property line: 225 ft 19. Distance to nearest well permitted/completed in the same formation: 828 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
J SAND	JSND	232	320	N/2
NIOBRARA-CODELL	NB-CD	407	80	N/2NW/4

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: _____

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

PLEASE SEE ATTACHED OGL.

25. Distance to Nearest Mineral Lease Line: 660 ft

26. Total Acres in Lease: 407

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☒ Offsite ☐ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☒ Land Spreading ☐ Disposal Facility Other: _____

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	8+5/8	24	0	900	630	900	0
1ST	7+7/8	4+1/2	11.6	0	8,339	200	8,339	

32. BOP Equipment Type: ☒ Annular Preventer ☐ Double Ram ☒ Rotating Head ☐ None

33. Comments NO CONDUCTOR CASING WILL BE USED.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: REBECCA HEIM

Title: REGULATORY ANALYST II Date: 7/12/2011 Email: DJREGULATORY@

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline

Director of COGCC Date: 8/7/2011

API NUMBER

05 123 34102 00

Permit Number: _____ Expiration Date: 8/6/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Jim Precup at 303-469-1902 or e-mail at james.precup@state.co.us
- 2) Comply with Rule 317.i and provide cement coverage from TD to a minimum of 200' above Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from TD to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
1694235	WELL LOCATION PLAT
1694236	TOPO MAP
1694237	OIL & GAS LEASE
400157786	APD APPROVED
400157788	OIL & GAS LEASE
400157790	PLAT
400157791	TOPO MAP
400157792	SURFACE AGRMT/SURETY
400157793	SURFACE AGRMT/SURETY
400157794	EXCEPTION LOC REQUEST
400184272	30 DAY NOTICE LETTER
400184273	DEVIATED DRILLING PLAN
400192945	FORM 2 SUBMITTED

Total Attach: 13 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Agency	Wellhead is to be located outside of a GWA drilling window and will be located more than 50' from an existing well location: EXCEPTION GRANTED.	8/7/2011 10:29:21 PM
Permit	Received and attached the correct Well Plat, Topo, O&G lease.	7/18/2011 3:03:11 PM
Permit	Requesting a corrected Well Plat, Topo, O&G lease.	7/18/2011 2:21:51 PM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)