

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400181054

PluggingBond SuretyID

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER ☐  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refilling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Julia Carter Phone: (720)876.5240 Fax: (720)876.6240

Email: Julia.Carter@encana.com

7. Well Name: SG Well Number: 8513E-25 D36496

8. Unit Name (if appl): Story Gulch Unit Number: COC69333X

9. Proposed Total Measured Depth: 13073

WELL LOCATION INFORMATION

10. QtrQtr: Lot 4 Sec: 36 Twp: 4S Rng: 96W Meridian: 6

Latitude: 39.664961 Longitude: -108.122864

Footage at Surface: 396 feet FNL/FSL 1042 feet FEL/FWL  
FNL FWL

11. Field Name: Grand Valley Field Number: 31250

12. Ground Elevation: 8290 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/01/2009 PDOP Reading: 1.9 Instrument Operator's Name: Greg Olsen

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 372 FSL 676 FWL 372 FSL 676 FWL  
Bottom Hole: FNL/FSL 372 FSL 676 FWL  
Sec: 25 Twp: 4S Rng: 96W Sec: 25 Twp: 4S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 31129 ft

18. Distance to nearest property line: 2760 ft 19. Distance to nearest well permitted/completed in the same formation: 198 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES			
Williams Fork	WMFK			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC61136

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T4S-R96W, Sec 25: ALL

25. Distance to Nearest Mineral Lease Line: 372 ft

26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle & Bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20	Line Pipe	0	120		120	0
SURF	14+3/4	9+5/8	36#	0	3,000	939	3,000	0
1ST	7+7/8	4+1/2	11.6#	0	13,073	1,342	13,073	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Encana Oil & Gas (USA) Inc owns surface. Please note the cement will be run to surface for both conductor and surface casing. The surface casing hole size will be 14-3/4", 12-1/4" or 13-1/2". Production casing hole size will be both 7-7/8" and 8-3/4". Production casing cement top will be 200' above WMFK. Distance on #17 taken from nearest above ground utility. Onsite was 8/12/2009 with BLM and CDOW.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julia M. Carter

Title: Regulatory Analyst Date: 6/30/2011 Email: Julia.Carter@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline

Director of COGCC Date: 8/7/2011

#### API NUMBER

05 045 20921 00

Permit Number: \_\_\_\_\_ Expiration Date: 8/6/2013

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2) GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3) THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400181054	APD APPROVED
400181069	LEASE MAP
400181070	OTHER
400181075	FED. DRILLING PERMIT
400181076	WELL LOCATION PLAT
400181077	TOPO MAP
400181399	DEVIATED DRILLING PLAN
400193006	FORM 2 SUBMITTED

Total Attach: 8 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Added field as Grand Valley Renamed attachment from Plat to Well Location Plat	3/2/2011 4:59:48 PM
Permit	Deviated drill plan attachment will not open. SJF	7/1/2011 8:10:24 AM

Total: 2 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)