

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400181149

PluggingBond SuretyID

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☐

Refilling ☐

Sidetrack ☐

3. Name of Operator: ENCANA OIL & GAS (USA) INC

4. COGCC Operator Number: 100185

5. Address: 370 17TH ST STE 1700

City: DENVER State: CO Zip: 80202-5632

6. Contact Name: Julia Carter Phone: (720)876.5240 Fax: (720)876.6240

Email: Julia.Carter@encana.com

7. Well Name: SG Well Number: 8515C-25 D36496

8. Unit Name (if appl): Story Gulch Unit Number: COC69333X

9. Proposed Total Measured Depth: 13580

WELL LOCATION INFORMATION

10. QtrQtr: Lot 4 Sec: 36 Twp: 4S Rng: 96W Meridian: 6

Latitude: 39.665022 Longitude: -108.122800

Footage at Surface: 373 feet FNL/FSL 1061 feet FEL/FWL  
FNL FWL

11. Field Name: Grand Valley Field Number: 31290

12. Ground Elevation: 8290 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 08/01/2009 PDOP Reading: 1.8 Instrument Operator's Name: Greg Olsen

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL 779 FSL 1996 FEL 779 FSL 1996 FEL  
Sec: 25 Twp: 4S Rng: 96W Sec: 25 Twp: 4S Rng: 96W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 31129 ft

18. Distance to nearest property line: 2768 ft 19. Distance to nearest well permitted/completed in the same formation: 199 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	ILES			
Williams Fork	WMFK			

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC61136

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T4S-R96W, Sec 25: ALL

25. Distance to Nearest Mineral Lease Line: 779 ft

26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☒ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Recycle & Bury

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	26	20	Line Pipe	0	120		120	0
SURF	14+3/4	9+5/8	36#	0	3,000	939	3,000	0
1ST	7+7/8	4+1/2	11.6#	0	13,580	1,417	13,580	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☐ Rotating Head ☐ None

33. Comments Encana Oil & Gas (USA) Inc owns surface. Please note the cement will be run to surface for both conductor and surface casing. The surface casing hole size will be 14-3/4", 12-1/4" or 13-1/2". Production casing hole size will be both 7-7/8" and 8-3/4". Production casing cement top will be 200' above WMFK. Distance on #17 taken from nearest above ground utility. Onsite was 8/12/2009 with BLM and CDOW.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☒ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Julia M. Carter

Title: Regulatory Analyst Date: 6/30/2011 Email: Julia.Carter@encana.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 8/7/2011

#### API NUMBER

05 045 20933 00

Permit Number: \_\_\_\_\_ Expiration Date: 8/6/2013

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

1)COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

2)GARFIELD COUNTY RULISON FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE

3)THE PROPOSED SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1 MILE IS 000 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400181149	APD APPROVED
400181160	LEASE MAP
400181161	OTHER
400181176	DEVIATED DRILLING PLAN
400181177	FED. DRILLING PERMIT
400181178	WELL LOCATION PLAT
400181400	TOPO MAP
400193026	FORM 2 SUBMITTED

Total Attach: 8 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Added field as Grand Valley Renamed attachment from Plat to Well Location Plat	3/2/2011 5:08:27 PM
Permit	Topo attachment will not open.	7/1/2011 7:33:56 AM

Total: 2 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)