

FORM
2Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER Horizontal
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐Refiling ☐Sidetrack ☒

Document Number:

400181788

PluggingBond SuretyID

20100108

3. Name of Operator: CARRIZO OIL & GAS INC4. COGCC Operator Number: 103385. Address: 1000 LOUISIANA STREET #1500City: HOUSTON State: TX Zip: 770026. Contact Name: Terry Hoffman Phone: (720)542-8287 Fax: (720)542-9213Email: terry@rockymountainpermitting.com7. Well Name: Speaker Well Number: 2-27-31-8-61

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 10665

WELL LOCATION INFORMATION

10. QtrQtr: NWNE Sec: 27 Twp: 8N Rng: 61W Meridian: 6Latitude: 40.639230 Longitude: -104.188060Footage at Surface: 307 feet FNL 1560 feet FEL11. Field Name: Wildcat Field Number: 9999912. Ground Elevation: 4992 13. County: WELD

14. GPS Data:

Date of Measurement: 06/09/2011 PDOP Reading: 2.3 Instrument Operator's Name: Marc Woodard15. If well is ☐ Directional ☒ Horizontal (highly deviated) **submit deviated drilling plan.**Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
650 FNL 2160 FEL 650 FSL 2160 FEL
Sec: 27 Twp: 8N Rng: 61W Sec: 27 Twp: 8N Rng: 61W16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No17. Distance to the nearest building, public road, above ground utility or railroad: 240 ft18. Distance to nearest property line: 307 ft 19. Distance to nearest well permitted/completed in the same formation: 1201 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR	535-13	640	All

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#: _____23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☒ Yes ☐ No23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T8N-R61W: Section 27: All; Section 28: E2; Section 35: N2NW4, SW4NW4 & NW4SW4

25. Distance to Nearest Mineral Lease Line: 307 ft

26. Total Acres in Lease: 1120

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Land Farming

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,400	534	1,400	0
1ST	8+3/4	7	23	0	6,666	635	6,666	1,400
2ND	6+1/8	4+1/2	11.6	0	10,665	350	10,665	5,666

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments No conductor casing will be set. All footages 5280' are 1 mile or greater. This is a two-well pad: Speaker 1-27-31-8-61 is 1st well on this pad and is closest well permitted in same formation.

34. Location ID: 424603

35. Is this application in a Comprehensive Drilling Plan? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: Terry L. Hoffman

Title: Permit Agent

Date: 7/8/2011

Email: terry@rockymountainpermitting.

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin

Director of COGCC Date: 8/7/2011

API NUMBER

05 123 34098 01

Permit Number: _____ Expiration Date: 8/6/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 24 hour notice of MIRU to Bo Brown via e-mail at bo.brown@state.co.us.
- 2) Comply with Rule 317.i and provide cement coverage from the end of the production casing to a minimum of 200' above the Niobrara. Verify coverage with cement bond log.
- 3) Comply with Rule 321. Run and submit Directional Survey from the end of production casing to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
2481063	SURFACE CASING CHECK
400181788	APD APPROVED
400183020	WELL LOCATION PLAT
400183021	DEVIATED DRILLING PLAN
400184088	OIL & GAS LEASE
400192977	FORM 2 SUBMITTED

Total Attach: 6 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	This is a pilot/lateral drilling plan. The permits will be on hold pending the completion of the 20 day public comment period at which time they will be approved together to maintain proper API number designations.	7/12/2011 9:21:23 AM
Permit	Social Security # on Oil Lease attachment.	7/11/2011 10:10:03 AM
Permit	Social Security # on Lease.	7/8/2011 3:08:10 PM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
Construction	<p>Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion.</p> <p>Operator will implement best management practices to contain any unintentional release of fluids.</p> <p>Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.</p> <p>Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use.</p> <p>Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit.</p> <p>Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source.</p> <p>The location will be fenced and the fenced area will include the Fresh Water Storage Pit.</p> <p>The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.</p>

Total: 1 comment(s)