

**FORM  
5**Rev  
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400156829

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 10079

4. Contact Name: Hannah Knopping

2. Name of Operator: ANTERO RESOURCES PICEANCE CORPORATION

Phone: (303) 357-6412

3. Address: 1625 17TH ST STE 300

Fax: (303) 357-7315

City: DENVER State: CO Zip: 80202

5. API Number 05-045-14370-00

6. County: GARFIELD

7. Well Name: Dixon Federal

Well Number: B5

8. Location: QtrQtr: NWSW Section: 15 Township: 6S Range: 92W Meridian: 6

Footage at surface: Distance: 1595 feet Direction: FSL Distance: 797 feet Direction: FWL

As Drilled Latitude: 39.524155 As Drilled Longitude: -107.659642

## GPS Data:

Date of Measurement: 04/11/2011 PDOP Reading: 1.4 GPS Instrument Operator's Name: Scott E. Aibner

\*\* If directional footage at Top of Prod. Zone Dist.: 2031 feet. Direction: FSL Dist.: 1986 feet. Direction: FWL

Sec: 15 Twp: 6S Rng: 92W

\*\* If directional footage at Bottom Hole Dist.: 2042 feet. Direction: FSL Dist.: 1985 feet. Direction: FWL

Sec: 15 Twp: 6S Rng: 92W

9. Field Name: MAMM CREEK

10. Field Number: 52500

11. Federal, Indian or State Lease Number: COC65762

12. Spud Date: (when the 1st bit hit the dirt) 03/05/2011 13. Date TD: 03/10/2011 14. Date Casing Set or D&amp;A: 03/11/2011

## 15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7730 TVD\*\* 7482 17 Plug Back Total Depth MD 7674 TVD\*\* 7426

18. Elevations GR 5513 KB 5537

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

## 19. List Electric Logs Run:

Mud Log, CBL and Triple Combo

## 20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
CONDUCTOR	24	16	75#	0	84	177	0	84	CALC
SURF	12+1/4	8+5/8	32#	0	1,035	290	0	1,035	CALC
1ST	7+7/8	4+1/2	11.6#	0	7,720	1,023	2,050	7,730	CBL

**ADDITIONAL CEMENT**

Cement work date: \_\_\_\_\_

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

21. Formation log intervals and test zones:

**FORMATION LOG INTERVALS AND TEST ZONES**

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
MESAVERDE	3,941		<input type="checkbox"/>	<input type="checkbox"/>	
CAMEO	6,546		<input type="checkbox"/>	<input type="checkbox"/>	
ROLLINS	7,556		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

All casing depths are reported from KB.

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Hannah KnoppingTitle: Permit Representative Date: 5/17/2011 Email: hknopping@anteroresources.com**Attachment Check List**

Att Doc Num	Document Name	attached ?			
<u>Attachment Checklist</u>					
400162820	CMT Summary *	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Core Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
400162822	Directional Survey **	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	DST Analysis	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
	Logs	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
	Other	Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
<u>Other Attachments</u>					
400156829	FORM 5 SUBMITTED	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400162818	PLAT	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400165660	LAS-CEMENT BOND	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400165667	LAS-MUD	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
400165671	LAS-TRIPLE COMBINATION	Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>

**General Comments**

User Group	Comment	Comment Date
------------	---------	--------------

--	--	--

Total: 0 comment(s)