

**FORM
5**Rev
02/08**State of Colorado****Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400182933

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 100322

4. Contact Name: EILEEN ROBERTS

2. Name of Operator: NOBLE ENERGY INC

Phone: (303) 2284330

3. Address: 1625 BROADWAY STE 2200

Fax: (303) 2284286

City: DENVER State: CO Zip: 80202

5. API Number 05-123-32722-00

6. County: WELD

7. Well Name: RICHTER USX AB

Well Number: 27-25

8. Location: QtrQtr: NWSW Section: 27 Township: 7N Range: 64W Meridian: 6

Footage at surface: Distance: 1520 feet Direction: FSL Distance: 1160 feet Direction: FWL

As Drilled Latitude: 40.541140 As Drilled Longitude: -104.541480

GPS Data:

Date of Measurement: 04/04/2011 PDOP Reading: 4.7 GPS Instrument Operator's Name: Paul Tappy

** If directional footage at Top of Prod. Zone Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

** If directional footage at Bottom Hole Dist.: feet. Direction: Dist.: feet. Direction:

Sec: Twp: Rng:

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 03/22/2011 13. Date TD: 03/25/2011 14. Date Casing Set or D&A: 03/25/2011

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7294 TVD** 17 Plug Back Total Depth MD 7193 TVD**

18. Elevations GR 4865 KB 4878

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

GRL/CCL/CBL/VDL, CDL/CNL/ML, HRIL.

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24.00	0	806	305	0	806	VISU
1ST	7+7/8	4+1/2	11.60	0	7,283	600	1,553	7,283	CBL

ADDITIONAL CEMENT

Cement work date: _____					
Details of work:					
Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES					
FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
NIOBRARA	6,838		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,081		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,105		<input type="checkbox"/>	<input type="checkbox"/>	
GREENHORN	7,184		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

--

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Eileen Roberts

Title: Regulatory Specialist Date: 7/8/2011 Email: eroberts@nobleenergyinc.com

Attachment Check List

Att Doc Num	Document Name	attached ?
<u>Attachment Checklist</u>		
400183027	CMT Summary *	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>
	Core Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Directional Survey **	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	DST Analysis	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Logs	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
	Other	Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>
<u>Other Attachments</u>		
400182933	FORM 5 SUBMITTED	Yes <input checked="" type="checkbox"/> No <input type="checkbox"/>

General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)