



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199626

Date 5/16/2011	Well Owner Kerr McGee	Well No. 26-5	Lease RET
County WELD	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700	(XTREME # 11)		
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	FL	
Surface 8 5/8" CSG 24"	Bottom of Surface	FL	
Plug	Plug Landed @ 683	FL	Time On 0830
Production	Pipe Landed @ 727	FL	Plug Down 0950

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TVIX III	460	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	78	Miles		
Fuel Surcharge	78	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	0907	0911
Disp. Rate	5 BPM	Mixing	0911	0939
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0939	0941
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0941	0950
Water/Cement	6.25 Gal/SK			2045540
Water Temp.	41			80012090 D22k
Total Slurry Vol.	109.7	BBLs Cement		
Landed Plug @	350	PSI/Final Lift @ 115	PSI	
Pre-Flush W/	20	BBLs H ₂ O	Tax Reference Code	Sub Total
Displace W/	43.4	BBLs H ₂ O	State CO 2.9%	Tax
Circulate	5	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		26			
1214/1218		Bulk Truck		26/26			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JIM/ADAM/STEVE/CRIS**

Received By **B. Benjamin**
Customer or His Agent