



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 199628

Date	5/19/2011	Well Owner	Kerr McGee	Well No.	27-5	Lease	RET
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME #11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	741		
Surface	8 3/8 CSG 24"	Bottom of Surface		Fl.	727		
Plug		Plug Landed @	683	Fl.	Time On	1330	
Production		Pipe Landed @	727	Fl.	Plug Down	1530	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	460	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	72	Miles		
Fuel Surcharge	72	MILES		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1447	1451
Disp. Rate	5 BPM	Mixing	1451	1518
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1518	1521
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1521	1530
Water/Cement	6.25 Gal/SK			
Water Temp.	41			
Total Slurry Vol.	109.1	BBLs Cement		
Landed Plug @	375	PSI/Final Lift @	260	PSI
Pre-Flush W/	20	BBLs H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	43.4	BBLs H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	5	BBLs Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		24			
1207/1216		Bulk Truck		24/24			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/ADAM/STEVE/CRIS

Received By [Signature]  
Customer or His Agent