



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199641

Date	5-30-11	Well Owner	Kerr McGee	Well No.	39-9	Lease	RET
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-11)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	800		
Surface	8 5/8" CSG - 244	Bottom of Surface		Ft.	784		
Plug		Plug Landed @	738	Ft.	Time On	1045	
Production		Pipe Landed @	784	Ft.	Plug Down	1400	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III 100% EXCESS	500	SKS		
Poz. Mix				
Calcium Chloride	2046962 DRL	2.5	%	
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	800/2 090	102	Miles	
Fuel Surcharge		102	MILES	
Additional Cement	TOP JOB	40	SKS	
Mixing Rate	4 BPM	Pre-Flush	1310	1315
Disp. Rate	5 BPM	Mixing	1315	1347
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	1347	1350
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1350	1400
Water/Cement	6.25 Gal/SK			
Water Temp.	64°F			
Total Slurry Vol.	126.9	BBLS Cement		
Landed Plug @	280	PSI/Final Lift @	260	PSI
Pre-Flush Wt	20	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace Wt	46.9	BBLS H ₂ O	State	CO 2.9%
Circulate	Ø	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		34			
1214/1216		Bulk Truck		341/34			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, KENNY

Received By Tom Bower

Customer or His Agent