

FORM
5Rev
02/08

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400196051

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120 4. Contact Name: Cindy Vue
 2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6832
 3. Address: P O BOX 173779 Fax: (720) 929-7832
 City: DENVER State: CO Zip: 80217-

5. API Number 05-123-33495-00 6. County: WELD
 7. Well Name: REI Well Number: 25-9
 8. Location: QtrQtr: SENE Section: 9 Township: 3N Range: 65W Meridian: 6
 Footage at surface: Distance: 2157 feet Direction: FNL Distance: 696 feet Direction: FEL
 As Drilled Latitude: 40.241187 As Drilled Longitude: -104.661588

GPS Data:

Data of Measurement: 06/24/2011 PDOP Reading: 2.6 GPS Instrument Operator's Name: Renee Doiron

** If directional footage

at Top of Prod. Zone Distance: 2525 feet Direction: FNL Distance: 2530 feet Direction: FEL
 Sec: 9 Twp: 3N Rng: 65W
 at Bottom Hole Distance: 2527 feet Direction: FNL Distance: 2522 feet Direction: FEL
 Sec: 9 Twp: 3N Rng: 65W

9. Field Name: WATTENBERG 10. Field Number: 90750

11. Federal, Indian or State Lease Number: _____

12. Spud Date: (when the 1st bit hit the dirt) 06/02/2011 13. Date TD: 06/04/2011 14. Date Casing Set or D&A: 06/05/2011

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation
16. Total Depth MD 8102 TVD 7764 17 Plug Back Total Depth MD 8070 TVD 773218. Elevations GR 4816 KB 4831

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

CD-CN-ML, HRI; CBL

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	787	540	0	787	CALC
1ST	7+7/8	4+1/2	11.6#	0	8,092	232	6,330	8,092	CBL

ADDITIONAL CEMENT

Cement work date: 06/05/2011

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	5,169	626	794	5,216

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,054		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,580	4,816	<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,188		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,451		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,479		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	7,930		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: _____ Email: Cindy.Vue@anadarko.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name
400196064	DIRECTIONAL SURVEY
400196066	CEMENT JOB SUMMARY

Total Attach: 2 Files

General Comments

User Group Comment Comment Date

--	--	--

Total: 0 comment(s)