



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 199677

Date <b>6/6/11</b>	Well Owner <b>Kerr McGee</b>	Well No. <b>21-9</b>	Lease <b>REI</b>
County <b>WELD</b>	State <b>Colorado</b>		
Charge to <b>Kerr McGee Oil &amp; Gas Onshore, LP</b>			
Address <b>1999 Broadway, Suite 3700</b>	<b>(XTREME II)</b>		
City, State Zip <b>Denver, Colorado 80202</b>			
Type of Job	Depth	Ft. <b>8382</b>	
<u>Surface</u> <b>8 5/8" CSG-24"</b>	Bottom of Surface	Ft. <b>817</b>	
Plug	Plug Landed @ <b>773</b>	Ft. <b>Time On 2230</b>	
Production	Pipe Landed @ <b>817</b>	Ft. <b>Plug Down 0500</b>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <b>TYPE III</b>	<b>520</b>	SKS		
Poz. Mix				
Calcium Chloride	<b>2046961 ARL</b>	2.5 %		
Gel % Flo-Crete 1/4 # Per Sack				
Mileage Charge <b>80012090</b>	<b>132</b>	Miles		
Fuel Surcharge	<b>132</b>			
Additional Cement		SKS		
Mixing Rate <b>4 BPM</b>	Pre-Flush	<b>0413</b>	<b>0417</b>	
Disp. Rate <b>5 BPM</b>	Mixing	<b>0417</b>	<b>0447</b>	
Slurry Vol. <b>1.32<sup>3</sup> Cu.Ft./Sk</b>	Change Valves	<b>0447</b>	<b>0450</b>	
Slurry Wt. <b>14.8 - 15.0 PPG</b>	Displacement	<b>0450</b>	<b>0500</b>	
Water/Cement <b>6.25 Gal/SK</b>				
Water Temp. <b>40</b>				
Total Slurry Vol. <b>122.2</b>	BBLS Cement			
Landed Plug @ <b>350</b>	PSI/Final Lift @ <b>175</b>	PSI		
Pre-Flush Wt/ <b>20</b>	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total	
Displace Wt/ <b>49.1</b>	BBLS H <sub>2</sub> O	State <b>CO 2.9%</b>	Tax	
Circulate <b>7</b>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<b>1201</b>		Pump Truck		<b>44</b>			
<b>1216/1218</b>		Bulk Truck		<b>44/44</b>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **Jim, Adam, Chris, Justin**

Received By **Tom Bauer**  
Customer or His Agent