

FORM  
5A

Rev  
02/08

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400196421

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 47120 4. Contact Name: CARA MAHLER  
2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP Phone: (720) 929-6029  
3. Address: P O BOX 173779 Fax: (720) 929-7029  
City: DENVER State: CO Zip: 80217-

5. API Number 05-123-21918-00 6. County: WELD  
7. Well Name: CAMP Well Number: 17-25  
8. Location: QtrQtr: NWNE Section: 25 Township: 3N Range: 66W Meridian: 6  
9. Field Name: \_\_\_\_\_ Field Code: \_\_\_\_\_

Completed Interval

FORMATION: NIOBARRA-CODELL Status: PRODUCING  
Treatment Date: 07/18/2011 Date of First Production this formation: 08/05/2011  
Perforations Top: 7209 Bottom: 7462 No. Holes: 170 Hole size: 0.38  
Provide a brief summary of the formation treatment: \_\_\_\_\_ Open Hole: ☐  
REPERF CDL (7/7/2011) 7448-7462 HOLES 28 SIZE .38  
Re-Frac Codell down 4-1/2" Csg w/ 273,756 gal Slickwater w/ 209,360# 40/70, 4,000# SuperLC.  
This formation is commingled with another formation: ☐ Yes ☒ No  
**Test Information:**  
Date: 08/13/2011 Hours: 24 Bbls oil: 25 Mcf Gas: 276 Bbls H2O: 0  
Calculated 24 hour rate: Bbls oil: 25 Mcf Gas: 276 Bbls H2O: 0 GOR: 11040  
Test Method: FLOWING Casing PSI: 906 Tubing PSI: 648 Choke Size: 18/64  
Gas Disposition: SOLD Gas Type: WET BTU Gas: 1244 API Gravity Oil: 55  
Tubing Size: 2 + 3/8 Tubing Setting Depth: 7426 Tbg setting date: 08/02/2011 Packer Depth: \_\_\_\_\_  
Reason for Non-Production: \_\_\_\_\_  
Date formation Abandoned: \_\_\_\_\_ Squeeze: ☐ Yes ☐ No If yes, number of sacks cmt \_\_\_\_\_  
Bridge Plug Depth: \_\_\_\_\_ Sacks cement on top: \_\_\_\_\_

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: CARA MAHLER  
Title: REGULATORY ANALYST 1 Date: \_\_\_\_\_ Email CARA.MAHLER@ANADARKO.COM

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

**Attachment Check List**

Att Doc Num	Name

Total Attach: 0 Files

**General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>

Total: 0 comment(s)