

FORM
2

Rev
12/05

State of Colorado

Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400189319

PluggingBond SuretyID

20030009

APPLICATION FOR PERMIT TO:

1. Drill, Deepen, Re-enter, Recomplete and Operate

2. TYPE OF WELL

OIL GAS COALBED OTHER _____
SINGLE ZONE MULTIPLE COMMINGLE

Refiling

Sidetrack

3. Name of Operator: NOBLE ENERGY INC

4. COGCC Operator Number: 100322

5. Address: 1625 BROADWAY STE 2200

City: DENVER State: CO Zip: 80202

6. Contact Name: JAN KAJIWARA Phone: (303)228-4092 Fax: (303)228-4286

Email: jkajiwara@nobleenergyinc.com

7. Well Name: CANNON H Well Number: 35-22X

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 7760

WELL LOCATION INFORMATION

10. QtrQtr: NWSE Sec: 35 Twp: 3N Rng: 65W Meridian: 6

Latitude: 40.181180 Longitude: -104.626500

Footage at Surface: 2492 feet FSL 1320 feet FEL

11. Field Name: WATTENBERG Field Number: 90750

12. Ground Elevation: 4739 13. County: WELD

14. GPS Data:

Date of Measurement: 04/12/2010 PDOP Reading: 1.6 Instrument Operator's Name: ROBERT DALEY

15. If well is Directional Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL
2550 FSL 1589 FEL 2550 FSL 1589 FEL
Sec: 35 Twp: 3N Rng: 65W Sec: 35 Twp: 3N Rng: 65W

16. Is location in a high density area? (Rule 603b)? Yes No

17. Distance to the nearest building, public road, above ground utility or railroad: 3335 ft

18. Distance to nearest property line: 155 ft 19. Distance to nearest well permitted/completed in the same formation: 730 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
CODELL	CODL	407-87	160	GWA
J SAND	JSND	232-23	160	GWA
NIOBRARA	NBRR	407-87	160	GWA

21. Mineral Ownership: Fee State Federal Indian Lease #: _____

22. Surface Ownership: Fee State Federal Indian

23. Is the Surface Owner also the Mineral Owner? Yes No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? Yes No

23b. If 23 is No: Surface Owners Agreement Attached or \$25,000 Blanket Surface Bond \$2,000 Surface Bond \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

SEE SUA AND LEASE INFORMATION FILED WITH ORIGINAL APD

25. Distance to Nearest Mineral Lease Line: 89 ft 26. Total Acres in Lease: 5709

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? Yes No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? Yes No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? Yes No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? Yes No

31. Mud disposal: Offsite Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: Land Farming Land Spreading Disposal Facility Other: CLOSED LOOP

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
1ST	7+7/8	4+1/2	11.6	0	7,760	733	7,760	

32. BOP Equipment Type: Annular Preventer Double Ram Rotating Head None

33. Comments NO CONDUCTOR CASING WILL BE USED. 1ST STRING TOP OF CEMENT = 200' ABOVE NIOBRARA. PROPOSED SPACING UNIT IS S/2NE/4 AND THE N/2SE/4.

34. Location ID: _____

35. Is this application in a Comprehensive Drilling Plan ? Yes No

36. Is this application part of submitted Oil and Gas Location Assessment ? Yes No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: JAN KAJIWARA

Title: REGULATORY ANALYST Date: 7/27/2011 Email: jkajiwara@nobleenergyinc.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline Director of COGCC Date: 8/21/2011

API NUMBER

05 123 31866 01

Permit Number: _____ Expiration Date: 8/20/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Comply with Rule 317.i and provide cement coverage from the end of the production casing to a minimum of 200' above the Niobrara and from 200' below Sussex to 200' above Sussex. Verify coverage with a cement bond log.
- 2) Comply with Rule 321. Run and submit Directional Survey from the end of production casing to base of surface casing. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.

Attachment Check List

Att Doc Num	Name
2530903	WELL LOCATION PLAT
400189319	FORM 2 SUBMITTED
400190186	DEVIATED DRILLING PLAN

Total Attach: 3 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	Updated permit with new survey plat.	3/5/2011 9:05:58 AM
Permit	On hold waiting for survey plat.	7/27/2011 5:34:52 PM
Permit	This is a sidetrack to a faulted out vertical well. The well was directionally drilled to an offset BHL.	7/27/2011 5:29:41 PM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>
General Housekeeping	Housekeeping will consist of neat and orderly storage of materials and fluids. Wastes will be temporarily stored in sealed containers and regularly collected and disposed of at offsite, suitable facilities. If spills occur prompt cleanup is required to minimize any commingling of waste materials with stormwater runoff. Routine maintenance will be limited to fueling and lubrication of equipment. Drip pans will be used during routine fueling and maintenance to contain spills or leaks. Any waste product from maintenance will be containerized and transported offsite for disposal or recycling. There will be no major equipment overhauls conducted onsite. Equipment will be transported offsite for major overhauls. Cleanup of trash and discarded materials will be conducted at the end of each work day. Cleanup will consist of patrolling the roadway, access areas, and other work areas to pickup trash, scrap debris, other discarded materials, and any contaminated soil. These materials will be disposed of properly.
Storm Water/Erosion Control	Stormwater management plans (SWMP) are in place to address construction, drilling and operations associated with Oil & Gas development throughout the state of Colorado in accordance with Colorado Department of Public Health and Environment (CDPHE) General Permit No. COR-038637. BMP's will be constructed around the perimeter of the site prior to, or at the beginning of construction. BMP's used will vary according to the location, and will remain in place until the pad reaches final reclamation.
Material Handling and Spill Prevention	Spill Prevention Control and Countermeasures (SPCC) plans are in place to address any possible spill associated with Oil & Gas operations throughout the state of Colorado in accordance with CFR 112.

Total: 3 comment(s)