

FORM  
2

Rev  
12/05

# State of Colorado

## Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

### APPLICATION FOR PERMIT TO:

1.  Drill,  Deepen,  Re-enter,  Recomplete and Operate

#### 2. TYPE OF WELL

OIL  GAS  COALBED  OTHER Pilot Hole  
SINGLE ZONE  MULTIPLE  COMMINGLE

Refiling   
Sidetrack

Document Number:

400198429

Plugging Bond Surety

20100108

3. Name of Operator: CARRIZO OIL & GAS INC

4. COGCC Operator Number: 10338

5. Address: 1000 LOUISIANA STREET #1500

City: HOUSTON State: TX Zip: 77002

6. Contact Name: Tina Taylor Phone: (713)328-1000 Fax: (713)358-6440

Email: tina.taylor@crzo.net

7. Well Name: Barracuda Well Number: 20-14-7-60

8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_

9. Proposed Total Measured Depth: 6987

### WELL LOCATION INFORMATION

10. QtrQtr: SWSW Sec: 20 Twp: 7N Rng: 60W Meridian: 6

Latitude: 40.554520 Longitude: -104.125470

Footage at Surface: 400 feet FNL/FSL 600 feet FEL/FWL FWL

11. Field Name: Wildcat Field Number: 99999

12. Ground Elevation: 4974 13. County: WELD

#### 14. GPS Data:

Date of Measurement: 08/15/2011 PDOP Reading: 2.4 Instrument Operator's Name: George Allen

15. If well is  Directional  Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_ Bottom Hole: FNL/FSL \_\_\_\_\_ FEL/FWL \_\_\_\_\_

Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_ Sec: \_\_\_\_\_ Twp: \_\_\_\_\_ Rng: \_\_\_\_\_

16. Is location in a high density area? (Rule 603b)?  Yes  No

17. Distance to the nearest building, public road, above ground utility or railroad: 4637 ft

18. Distance to nearest property line: 400 ft 19. Distance to nearest well permitted/completed in the same formation: 850 ft

### 20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Niobrara	NBRR		640	W/2

21. Mineral Ownership:  Fee  State  Federal  Indian Lease #: \_\_\_\_\_

22. Surface Ownership:  Fee  State  Federal  Indian

23. Is the Surface Owner also the Mineral Owner?  Yes  No Surface Surety ID#: \_\_\_\_\_

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease?  Yes  No

23b. If 23 is No:  Surface Owners Agreement Attached or  \$25,000 Blanket Surface Bond  \$2,000 Surface Bond  \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

T7N R60W 6th P.M. Section 20: W/2

25. Distance to Nearest Mineral Lease Line: 0 ft 26. Total Acres in Lease: 640

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated?  Yes  No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling?  Yes  No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling?  Yes  No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)?  Yes  No

31. Mud disposal:  Offsite  Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method:  Land Farming  Land Spreading  Disposal Facility Other: Landfarm Burial/Evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
SURF	12+1/4	9+5/8	36	0	1,400	534	1,400	0
OPEN HOLE	8+3/4			1400	6,987	796	6,987	5,589

32. BOP Equipment Type:  Annular Preventer  Double Ram  Rotating Head  None

33. Comments This is a Pilot Hole for informational purposes only and will be plugged back at 6987' TD with 796 sacks of cement. Top of cement will be 5589'. No conductor casing will be set.

34. Location ID: \_\_\_\_\_

35. Is this application in a Comprehensive Drilling Plan ?  Yes  No

36. Is this application part of submitted Oil and Gas Location Assessment ?  Yes  No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Tina Taylor

Title: Regulatory Compliance Date: \_\_\_\_\_ Email: tina.taylor@crzo.net

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

API NUMBER

05

Permit Number: \_\_\_\_\_ Expiration Date: \_\_\_\_\_

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

\_\_\_\_\_

### Attachment Check List

Att Doc Num	Name
400198469	WELL LOCATION PLAT
400198470	DEVIATED DRILLING PLAN

Total Attach: 2 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)

### BMP

<u>Type</u>	<u>Comment</u>
Material Handling and Spill Prevention	Operator will ensure 110 percent secondary containment for any volume of fluids contained at the well site during drilling and completion. Operator will implement best management practices to contain any unintentional release of fluids.
Storm Water/Erosion Control	Operator has designed the well pad with insloping and a storm water control ditch to prevent storm water run-on/runoff and the release of fluids from the location. See attached Construction Layout Drawing.
Site Specific	Fresh water for the Fresh Water Storage Pit comes from water provider; water sources permitted for consumable industrial use.
Material Handling and Spill Prevention	Operator shall not allow any fluids to flow back to the Fresh Water Storage Pit/Pond.
Site Specific	Fresh Water Storage Pit shall contain fresh water only and signage prohibiting the use of the pit for any fluid that does not come from municipal, irrigation or surface water source.
Construction	The location will be fenced and the fenced area will include the Fresh Water Storage Pit.
Pre-Construction	The COGCC to be notified 48 hours prior to construction of the Fresh Water Storage Pit.
Planning	A Form 15 Pit Report will be submitted within 30 days of construction of the fresh water storage pit.

Total: 8 comment(s)