

FORM  
2

Rev  
12/05

State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
Document Number:  400175518			
PluggingBond SuretyID			

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☐ GAS ☒ COALBED ☐ OTHER \_\_\_\_\_  
SINGLE ZONE ☐ MULTIPLE ☒ COMMINGLE ☒

Refilling ☐  
Sidetrack ☐

3. Name of Operator: WILLIAMS PRODUCTION RMT COMPANY LLC 4. COGCC Operator Number: 96850  
5. Address: 1001 17TH STREET - SUITE #1200  
City: DENVER State: CO Zip: 80202  
6. Contact Name: Greg Davis Phone: (303)606-4071 Fax: (303)629-8268  
Email: Greg.J.Davis@Williams.com  
7. Well Name: Jolley Well Number: KP 323-8  
8. Unit Name (if appl): \_\_\_\_\_ Unit Number: \_\_\_\_\_  
9. Proposed Total Measured Depth: 7617

WELL LOCATION INFORMATION

10. QtrQtr: SESW Sec: 8 Twp: 6S Rng: 91W Meridian: 6  
Latitude: 39.535536 Longitude: -107.579792

Footage at Surface: 198 feet FSL 2326 feet FWL

11. Field Name: Kokopelli Field Number: 47525  
12. Ground Elevation: 6526 13. County: GARFIELD

14. GPS Data:

Date of Measurement: 12/14/2009 PDOP Reading: 2.5 Instrument Operator's Name: J. Kirkpatrick

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: FNL/FSL FEL/FWL Bottom Hole: FNL/FSL FEL/FWL  
2144 FSL 2009 FWL 2144 FSL 2009 FWL  
Sec: 8 Twp: 6S Rng: 91W Sec: 8 Twp: 6S Rng: 91W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 1790 ft

18. Distance to nearest property line: 1115 ft 19. Distance to nearest well permitted/completed in the same formation: 314 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Iles	Iles	513-5	320	S/2
Williams Fork	WMFK	513-4	320	S/2

21. Mineral Ownership: ☐ Fee ☐ State ☒ Federal ☐ Indian Lease #: COC51146

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☒ Yes ☐ No Surface Surety ID#:

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☒ No

23b. If 23 is No: ☒ Surface Owners Agreement Attached or ☐ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See attached.

25. Distance to Nearest Mineral Lease Line: 496 ft

26. Total Acres in Lease: 1200

### DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Re-use and evaporation

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	18	48#	0	45	25	45	0
SURF	13+1/2	9+5/8	32.3#	0	1,387	362	1,387	0
1ST	7+7/8	4+1/2	11.6#	0	7,617	704	7,617	

32. BOP Equipment Type: ☒ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Closed Loop. Cement 500' above top of gas. CA COC73368 See Williams Master APD. Surface owner owns minerals within the 320 acre S/2 communitization agreement.

34. Location ID: 336009

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_

Print Name: Greg Davis

Title: Supervisor Permits Date: 7/13/2011 Email: Greg.J.Davis@Williams.com

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Nesline

Director of COGCC Date: 8/26/2011

#### API NUMBER

05 045 20991 00

Permit Number: \_\_\_\_\_ Expiration Date: 8/25/2013

#### CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

(1) COMPLIANCE WITH THE MOST CURRENT REVISION OF THE NORTHWEST COLORADO NOTIFICATION POLICY IS REQUIRED.

(2) GARFIELD COUNTY RULISON-FIELD NOTICE TO OPERATORS. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(3) NEW MAMM CREEK FIELD NOTICE TO OPERATORS APPLIES TO THIS WELL. NOTE: ALL NOTICES SHALL BE GIVEN VIA E-MAIL. SEE ATTACHED NOTICE.

(4) COMPLIANCE WITH THE NOTICE TO OPERATORS DRILLING WELLS IN THE BUZZARD, MAMM CREEK, AND RULISON FIELDS, GARFIELD COUNTY AND MESA COUNTY – PROCEDURES AND SUBMITTAL REQUIREMENTS FOR COMPLIANCE WITH COGCC ORDER NOS. 1-107, 139-56, 191-22, AND 369-2 (JULY 8, 2010) -- IS REQUIRED. SEE ATTACHED NOTICE.

(5) THE MOISTURE CONTENT OF ANY DRILL CUTTINGS IN A CUTTINGS PIT, TRENCH, OR PILE SHALL BE AS LOW AS PRACTICABLE TO PREVENT ACCUMULATION OF LIQUIDS GREATER THAN DE-MINIMIS AMOUNTS. AT THE TIME OF CLOSURE, THE DRILL CUTTINGS MUST ALSO MEET THE APPLICABLE STANDARDS OF TABLE 910-1.

(6) NO PORTION OF ANY PIT THAT WILL BE USED TO HOLD LIQUIDS SHALL BE CONSTRUCTED ON FILL MATERIAL, UNLESS THE PIT AND FILL SLOPE ARE DESIGNED AND CERTIFIED BY A PROFESSIONAL ENGINEER, SUBJECT TO REVIEW AND APPROVAL BY THE DIRECTOR PRIOR TO CONSTRUCTION OF THE PIT. THE CONSTRUCTION AND LINING OF THE PIT SHALL BE SUPERVISED BY A PROFESSIONAL ENGINEER OR THEIR AGENT. THE ENTIRE BASE OF THE PIT MUST BE IN CUT.

(7) THE SURFACE CASING IS MORE THAN 50' BELOW THE DEPTH OF THE DEEPEST WATER WELL WITHIN 1 -MILE OF THE SURFACE LOCATION WHEN CORRECTED FOR ELEVATION DIFFERENCES. THE DEEPEST WATER WELL WITHIN 1-MILE IS 145 FEET DEEP.

### **Attachment Check List**

Att Doc Num	Name
400175518	FORM 2 SUBMITTED
400175811	WELL LOCATION PLAT
400175812	LEGAL/LEASE DESCRIPTION
400175816	SURFACE AGRMT/SURETY
400175818	TOPO MAP
400183218	DEVIATED DRILLING PLAN
400184648	FED. DRILLING PERMIT

Total Attach: 7 Files

### **General Comments**

<b><u>User Group</u></b>	<b><u>Comment</u></b>	<b><u>Comment Date</u></b>
Permit	Corrected spacing order for the Williams Fork formation	8/12/2011 11:56:54 AM
Engineer	waiting for decision regarding "deep fresh water" -- subject of Aug. 25 meeting with OPR, COGCC, and BLM (Silt). This may result in withdrawal of COA requiring production casing cemented into surface. 8/25: off "on hold" and cementing COA withdrawn	8/10/2011 3:40:44 PM

Total: 2 comment(s)

### **BMP**

<b><u>Type</u></b>	<b><u>Comment</u></b>

Total: 0 comment(s)