



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199719

Date 6-21-11	Well Owner Kerr McGee	Well No. 1-26 5x	Lease Bedding
County Weld	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700	(Xtreme #14)		
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	Ft. 1196	
Surface	8 5/8" CS6-24"	Bottom of Surface	Ft. 1128
Plug	Plug Landed @ 1084	Fl.	Time On 13:00
Production	Pipe Landed @ 1128	Fl.	Plug Down 16:30

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat ✓ Type III	710	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Fio-Cete 1/4 # Per Sack				
Mileage Charge	204	Miles		
Fuel Surcharge	204	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	1536	1542		
Pre-Flush				
Disp. Rate 5 BPM	1542	1613		
Mixing				
Slurry Vol. 1.32³ Cu.Ft./Sk	1613	1616		
Change Valves				
Slurry Wt. 14.8 - 15.0 PPG	1616	1630		
Displacement				
Water/Cement 6.25 Gal/SK				
Water Temp. 70 °F				
Total Slurry Vol. 167	BBLS Cement			
Landed Plug @ 750	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 69	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 6	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		68			
1214/1218		Bulk Truck		68/68			

We do not assume any responsibility for any damage or conditions resulting from our services. All prices subject to review and revision.

Delivered By **Justin, Dallas, Kenny, Demetrio**

Received By

Curly Sanders
Customer or His Agent