



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199627

Date <u>5/16/2011</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>24-6</u>	Lease <u>NICHOLS</u>				
County <u>WELD</u>	State <u>Colorado</u>						
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>							
Address <u>1999 Broadway, Suite 3700</u>	<u>(PATTERSON #159)</u>						
City, State Zip <u>Denver, Colorado 80202</u>							
Type of Job	Depth	FL <u>850</u>					
Surface <u>8 5/8 CSG 24"</u>	Bottom of Surface	FL <u>838</u>					
Plug	Plug Landed @ <u>794</u> Ft.	Time On <u>2200</u>					
Production	Pipe Landed @ <u>838</u> Ft.	Plug Down <u>0200</u>					
Description	Qty.	Meas.	Unit Price Amount				
Set Up Charge	1						
Cement Neat <u>TYPE III</u>	530	SKS					
Poz. Mix							
Calcium Chloride	2.5	%					
Gel % Flo-Cote 1/4 # Per Sack							
Mileage Charge <u>204048</u>	126	Miles					
Fuel Surcharge <u>2001 2090</u>	126	MILES					
Additional Cement		SKS					
Mixing Rate	4 BPM	Pre-Flush	0117	0123			
Disp. Rate	5 BPM	Mixing	0123	0146			
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0146	0149			
Slurry Wt.	14.8 - 15.0 PPG	Displacement	0149	0200			
Water/Cement	6.25 Gal/SK						
Water Temp.	<u>42</u>						
Total Slurry Vol.	<u>124.5</u>	BBLs Cement					
Landed Plug @	<u>375</u>	PSI/Final Lift @ <u>125"</u>	PSI				
Pre-Flush W/ <u>20</u>	BBLs H ₂ O	Tax Reference Code	Sub Total				
Displace W/ <u>50.5</u>	BBLs H ₂ O	State <u>CO 2.9%</u>	Tax				
Circulate <u>7</u>	BBLs Cement		Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1201</u>		Pump Truck		<u>42</u>			
<u>1214/1215</u>		Bulk Truck		<u>42/42</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/ADAM/STEVE/CRIS

Received By [Signature]

Customer or His Agent