



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199586

Date 5-4-11	Well Owner Kerr McGee	Well No. 23-32	Lease CARTER
County WELD	State Colorado		
Charge to Kerr McGee Oil & Gas Onshore, LP			
Address 1999 Broadway, Suite 3700 (XTREME-6)			
City, State Zip Denver, Colorado 80202			
Type of Job	Depth	Ft.	915
<u>Surface</u>	8 5/8" 15G-24#	Bottom of Surface	Ft. 905
Plug	Plug Landed @ 860	Fl.	Time On 1230
Production	Pipe Landed @ 905	Fl.	Plug Down 1500

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	570	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack 2053271 DM				
Mileage Charge 800/2090	186	Miles		
Fuel Surcharge	186	MILES		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	1404	1412	
Disp. Rate 5 BPM	Mixing	1412	1446	
Slurry Vol. 1.32° Cu.Ft./Sk	Change Valves	1446	1449	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1449	1500	
Water/Cement 6.25 Gall/SK				
Water Temp. 56°F				
Total Slurry Vol. 134.0	BBLs Cement			
Landed Plug @ 800	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 30	BBLs H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 54.6	BBLs H ₂ O	State CO 2.9%	Tax	
Circulate 6	BBLs Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		62			
1207/1217		Bulk Truck		62/162			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By **JOE, JOSH, EVAN, KERRY**

Received By **Mac'Noykwa**
Customer or His Agent