

**FORM  
5**Rev  
02/08**State of Colorado  
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400200710

**DRILLING COMPLETION REPORT**

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Emily Carrender

2. Name of Operator: KERR-MCGEE OIL &amp; GAS ONSHORE LP

Phone: (720) 929-6282

3. Address: P O BOX 173779

Fax: (720) 929-7282

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-32588-00

6. County: WELD

7. Well Name: COOK

Well Number: 21-9

8. Location: QtrQtr: SENW Section: 9 Township: 2N Range: 65W Meridian: 6

Footage at surface: Distance: 2374 feet Direction: FNL Distance: 2623 feet Direction: FWL

As Drilled Latitude: 40.154010 As Drilled Longitude: -104.668933

GPS Data:

Data of Measurement: 08/24/2011 PDOP Reading: 3.3 GPS Instrument Operator's Name: Renee Doiron

\*\* If directional footage

at Top of Prod. Zone Distance: 1328 feet Direction: FNL Distance: 2526 feet Direction: FWL

Sec: 9 Twp: 2N Rng: 65W

at Bottom Hole Distance: 1342 feet Direction: FNL Distance: 2525 feet Direction: FWL

Sec: 9 Twp: 2N Rng: 65W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 05/22/2011 13. Date TD: 05/25/2011 14. Date Casing Set or D&amp;A: 05/26/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 7950 TVD 7805 17 Plug Back Total Depth MD 7905 TVD 7760

18. Elevations GR 4872 KB 4887

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

PRE FORM 5

20. Casing, Liner and Cement:

**CASING**

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24.0	0	752	470	15	752	CALC
1ST	7+7/8	4+1/2	11.6	0	7,940	620	3,756	7,940	CALC

**ADDITIONAL CEMENT**

Cement work date: 05/25/2011

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	3,756	480	556	3,756

21. Formation log intervals and test zones:

### FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	4,065		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,375	4,704	<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,038		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	7,300		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,320		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	7,775		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Emily Carrender

Title: Operation Specialist I Date: \_\_\_\_\_ Email: emily.carrender@anadarko.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

### Attachment Check List

Att Doc Num	Name
400200727	DIRECTIONAL SURVEY
400200728	CEMENT JOB SUMMARY

Total Attach: 2 Files

### General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)