



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199639

Date	5-23-11	Well Owner	Kerr McGee	Well No.	21-9	Lessee	COOK
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-15)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	FL	761			
Surface	8 7/8" CSG-24#	Bottom of Surface	FL	751			
Plug		Plug Landed @	705	Time On	0715		
Production		Pipe Landed @	751	Plug Down	0900		
Description	Qty.	Meas.	Unit Price	Amount			
Set Up Charge	1						
Cement Neat	TYPE III	470	SKS				
Poz. Mix							
Calcium Chloride	2047651	2.5	%				
Gel %	Fio-Cete 1/4 # Per Sack	80012090					
Mileage Charge	120	Miles					
Fuel Surcharge	120	miles					
Additional Cement		SKS					
Mixing Rate	4 BPM	Pre-Flush	0815	0820			
Disp. Rate	5 BPM	Mixing	0820	0848			
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	0848	0851			
Slurry WL	14.8 - 15.0 PPG	Displacement	0851	0900			
Water/Cement	6.25 Gal/SK						
Water Temp.	60°F						
Total Slurry Vol.	110.5	BBLS Cement					
Landed Plug @	950	PSI/Final Lift @	300	PSI			
Pre-Flush W/	20	BBLS H ₂ O	Tax Reference Code	Sub Total			
Displace W/	44.8	BBLS H ₂ O	State CO 2.9%	Tax			
Circulate	4	BBLS Cement	Total				
Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		40			
1218/1214		Bulk Truck		40/40			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Joe, Josh, Evan, KENN Y

Received By *John Salas*
Customer or His Agent