



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 199662

Date	5/26/2011	Well Owner	Kerr McGee	Well No.	31-9	Lease	COOK
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME#15)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	Fl. 738				
Surface	8 5/8" CSG 24"	Bottom of Surface	Fl. 728				
Plug		Plug Landed @	684	Fl.	Time On 1330		
Production		Pipe Landed @	728	Fl.	Plug Down 1515		

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III 100% EXCESS	460	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	120	Miles		
Fuel Surcharge	120	MILES		
Additional Cement	40	SKS		
Mixing Rate	4 BPM	Pre-Flush	1432	1436
Disp. Rate	5 BPM	Mixing	1436	1503
Slurry Vol.	1.32 <sup>3</sup> Cu.Ft./Sk	Change Valves	1503	1506
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1506	1515
Water/Cement	6.25 Gal/SK			20475/15. DEL
Water Temp.	42			
Total Slurry Vol.	1175	BBLS Cement		800/120917
Landed Plug @	900	PSI/Final Lift @ 320	PSI	
Pre-Flush W/	20	BBLS H <sub>2</sub> O	Tax Reference Code	Sub Total
Displace W/	43.5	BBLS H <sub>2</sub> O	State CO 2.9%	Tax
Circulate	4	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		40			
1216/1217		Bulk Truck		40/40			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/ADAM/STUE/CRIS

Received By Rusty Tuck  
Customer or His Agent