



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199715

Date <u>6-16-11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>25-10</u>	Lease <u>REI</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #11)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	Fl. <u>785</u>	
<u>Surface</u>	<u>8 5/8" C56-24"</u>	Bottom of Surface	Fl. <u>772</u>
Plug	Plug Landed @ <u>728</u>	FL	Time On <u>04:50</u>
Production	Pipe Landed @ <u>772</u>	FL	Plug Down <u>07:15</u>

Description	Qty.	Meas.	Unit Price	Amount			
Set Up Charge	1						
Cement Neat <u>Type III</u>	490	SKS					
Poz. Mix							
Calcium Chloride	2.5	%					
Gel % Flo-Crete <u>1/4</u> # Per Sack							
Mileage Charge	108	Miles					
Fuel Surcharge	108	Miles					
Additional Cement		SKS					
Mixing Rate 4 BPM	0636	0642					
Disp. Rate 5 BPM	0642	0703					
Slurry Vol. 1.32 ³ Cu.Ft./Sk	0703	0706					
Slurry Wt. 14.8 - 15.0 PPG	0706	0715		2045968			
Water/Cement 6.25 Gal/SK				20012090 D210			
Water Temp. <u>68°F</u>							
Total Slurry Vol. <u>115.2</u> BBLS Cement							
Landed Plug @ <u>450</u> PSI/Final Lift @ <u>200</u> PSI							
Pre-Flush W/ <u>30</u> BBLS H ₂ O	Tax Reference Code		Sub Total				
Displace W/ <u>46.3</u> BBLS H ₂ O	State <u>CO 2.9%</u>		Tax				
Circulate <u>2</u> BBLS Cement			Total				
Truck No. <u>1208</u>	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
		Pump Truck		<u>36</u>			
<u>1217/1218</u>		Bulk Truck		<u>36/36</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin, Valle, Justin, Demetrio

Received By

B. Benjamin
Customer or His Agent