

**FORM
5**Rev
02/08**State of Colorado
Oil and Gas Conservation Commission**

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400201319

DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☐ Final completion ☒ Preliminary completion

1. OGCC Operator Number: 47120

4. Contact Name: Emily Carrender

2. Name of Operator: KERR-MCGEE OIL & GAS ONSHORE LP

Phone: (720) 929-6282

3. Address: P O BOX 173779

Fax: (720) 929-7282

City: DENVER State: CO Zip: 80217-

5. API Number 05-123-32849-00

6. County: WELD

7. Well Name: SWEETGRASS

Well Number: 13-14

8. Location: QtrQtr: NWSW Section: 14 Township: 1N Range: 68W Meridian: 6

Footage at surface: Distance: 2139 feet Direction: FSL Distance: 720 feet Direction: FWL

As Drilled Latitude: 40.049870 As Drilled Longitude: -104.977445

GPS Data:

Data of Measurement: 08/01/2011 PDOP Reading: 3.1 GPS Instrument Operator's Name: Renee Doiron

** If directional footage

at Top of Prod. Zone Distance: 641 feet Direction: FSL Distance: 664 feet Direction: FWL

Sec: 14 Twp: 1N Rng: 68W

at Bottom Hole Distance: 639 feet Direction: FSL Distance: 669 feet Direction: FWL

Sec: 14 Twp: 1N Rng: 68W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 06/05/2011 13. Date TD: 06/08/2011 14. Date Casing Set or D&A: 06/11/2011

15. Well Classification:

☐ Dry ☐ Oil ☒ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8796 TVD 8581 17 Plug Back Total Depth MD 8763 TVD 8548

18. Elevations GR 5105 KB 5120

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

PRE FORM 5

20. Casing, Liner and Cement:

CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24.0	0	1,191	850	15	1,191	CALC
1ST	7+7/8	4+1/2	11.6	0	8,779	300	6,916	8,779	CALC

ADDITIONAL CEMENT

Cement work date: 07/22/2011

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	6,395	800	630	6,395

21. Formation log intervals and test zones:

FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
PARKMAN	1,191		<input type="checkbox"/>	<input type="checkbox"/>	
SUSSEX	4,482		<input type="checkbox"/>	<input type="checkbox"/>	
SHANNON	5,473	5,885	<input type="checkbox"/>	<input type="checkbox"/>	
NIOBRARA	7,690		<input type="checkbox"/>	<input type="checkbox"/>	
FORT HAYS	8,053		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	8,074		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,520		<input type="checkbox"/>	<input type="checkbox"/>	
DAKOTA	8,671		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____ Print Name: Emily Carrender

Title: Operation Specialist I Date: _____ Email: emily.carrender@anadarko.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name
400201336	DIRECTIONAL SURVEY
400201337	CEMENT JOB SUMMARY

Total Attach: 2 Files

General Comments

User Group Comment Comment Date

--	--	--

Total: 0 comment(s)