



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199661

Date	5/25/2011	Well Owner	Kerr McGee	Well No.	12C-13H2	Lease	PSC
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME#8)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		FL	945		
Surface	9 7/8 CSO-36" 136HOLE	Bottom of Surface		Ft.	932		
Plug		Plug Landed @	888	Ft.	Time On	1210	
Production		Pipe Landed @	932	Ft.	Plug Down	1630	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE M	690	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Fio-Cete 1/4 # Per Sack				
Mileage Charge	2054094, DRL	192	Miles	
Fuel Surcharge	80012090	192	MILES	
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1527	1533
Disp. Rate	5 BPM	Mixing	1533	1613
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves	1613	1616
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1616	1630
Water/Cement	6.25 Gal/SK			
Water Temp.	47			
Total Slurry Vol.	162.2	BBLS Cement		
Landed Plug @	850	PSI/Final Lift @	375	PSI
Pre-Flush W/	30	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	68.5	BBLS H ₂ O	State CO 2.9%	Tax
Circulate	4	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		64			
1217/1218		Bulk Truck		64/64			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By: JIM/ADAM/STEVE/CRIS

Received By: Craig Jones
Customer or His Agent