



# CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

## 199706

Date	6-13-11	Well Owner	Kerr McGee	Well No.	12N13H2	Lease	PSC
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-8)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	1032		
Surface	9 5/8" CSG-36#-13 1/2" LUGS	Bottom of Surface		Ft.	1022		
Plug		Plug Landed @	980	Ft.	Time On	1400	
Production		Pipe Landed @	1022	Ft.	Plug Down	2045	

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat TYPE III	760	SKS
Poz. Mix		
Calcium Chloride	2.5	%
Gel % Flo-Cete 1/4 # Per Sack		
Mileage Charge	192	Miles
Fuel Surcharge	192	MILES
Additional Cement	2053810 D-1	SKS
Mixing Rate	4 BPM 800 12090	Pre-Flush 1934 -1942
Disp. Rate	5 BPM	Mixing 1942 -2027
Slurry Vol.	1.32 Cu.Ft/Sk	Change Valves 2027 -2030
Slurry Wt.	14.8 - 15.0 PPG	Displacement 2030 -2045
Water/Cement	6.25 Gal/SK	
Water Temp.	66°F	
Total Slurry Vol.	178.6	BBLS Cement
Landed Plug @	980	PSI/Final Lift @ 450 PSI
Pre-Flush W/	30	BBLS H <sub>2</sub> O
Displace W/	75.7	BBLS H <sub>2</sub> O
Circulate	6	BBLS Cement
Tax Reference Code		Sub Total
State CO 2.9%		Tax
		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		64			
1216/1218		Bulk Truck		64/64			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN ERNIE

Received By Customer or His Agent