



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199668

Date	6/28/11	Well Owner	Kerr McGee	Well No.	13C-13HZ	Lease	PSC
County		State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME 8)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth	Ft. 1046				
Surface	9 5/8" CSG 3 1/2" 13 1/2 HOLE	Bottom of Surface	Ft. 1037				
Plug		Plug Landed @	996	Ft.	Time On	2130	
Production		Pipe Landed @	1037	Ft.	Plug Down	0300	

Description	Qty.	Meas.
Set Up Charge	1	
Cement Neat TYPE III	770	SKS
Poz. Mix		
Calcium Chloride	2.5	%
Gel % Flo-Cete 1/4 # Per Sack		
Mileage Charge	128	Miles
Fuel Surcharge	128	MILES
Additional Cement		SKS
Mixing Rate	4 BPM	Pre-Flush
Disp. Rate	5 BPM	Mixing
Slurry Vol.	1.32 ³ Cu.Ft./Sk	Change Valves
Slurry Wt.	14.8 - 15.0 PPG	Displacement
Water/Cement	6.25 Gal/SK	
Water Temp.	65	
Total Slurry Vol.	181	BBLS Cement
Landed Plug @	790	PSI/Final Lift @ 300 PSI
Pre-Flush W/	30	BBLS H ₂ O
Displace W/	77	BBLS H ₂ O
Circulate	6	BBLS Cement
Tax Reference Code		Sub Total
State CO 2.9%		Tax
		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		64			
1234		Bulk Truck		64			

2054093.DRI

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JIM/ADAM/STEVE/CRIS/ADAM

Received By Rich Martin
Customer or His Agent