

TICKET NUMBER 28110

LOCATION Oaklev

FOREMAN Kelly Gabe

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-487-8676

FIELD TICKET & TREATMENT REPORT

CEMENT

621

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
7-23-11	5659	Terra 1-33	33	175	45 th	Kiowa
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS			463	Josh G		
			430	Dan M		
CITY						
STATE						
ZIP CODE						

JOB TYPE <u>54 PACE-0</u>	HOLE SIZE <u>12 1/4"</u>	HOLE DEPTH <u>336</u>	CASING SIZE & WEIGHT <u>8 3/8 24.2</u>
CASING DEPTH <u>324'</u>	DRILL PIPE	TUBING	OTHER
SLURRY WEIGHT <u>148</u>	SLURRY VOL <u>1.34</u>	WATER gal/sk <u>6.5</u>	CEMENT LEFT in CASING <u>20'</u>
DISPLACEMENT <u>19 1/4 bbl</u>	DISPLACEMENT PSI	MIX PSI	RATE

REMARKS: Safety meeting, rigged up on Martin d/s Rig #20 to circulate mixed slks com. 390cc 290gel. washed pump lines, & dispised with 19 1/4 bl itaz. was hed up + truck and pumps, racked up and 1st + 1009 + ion.

Content did circulate

THANKS

Kelly & Crew

[illegible]

Revin 3797

AUTHORIZATION

TITLE

TITLE Top Pusher

DATE 7-23-11

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



CONSOLIDATED
OIL WELL SERVICES, LLC

PO Box 884, Chanute, KS 66720
820-431-9210 or 800-467-8678

FIELD TICKET & TREATMENT REPORT

CEMENT

TICKET NUMBER 28116
LOCATION Oakley
FOREMAN Kelly Gabel

Col

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
8-5-11	5659	APC Tenna	33	175	450	Kiowa
CUSTOMER						
MAILING ADDRESS						
CITY						
STATE						
ZIP CODE						
			TRUCK #	DRIVER	TRUCK #	DRIVER
			399	Miles		
			460	Damon		

JOB TYPE Prod-O HOLE SIZE 2 7/8 HOLE DEPTH 5223 CASING SIZE & WEIGHT 5 1/2" K1
CASING DEPTH 5103 DRILL PIPE TUBING OTHER
SLURRY WEIGHT SLURRY VOL WATER gal/ek CEMENT LEFT IN CASING 42'
DISPLACEMENT 123 bbl DISPLACEMENT PSI MIX PSI RATE 6 bbl/min
REMARKS: Safety Meeting. Rigged upon Martin drilling Rig # 30
to circulate. Pumped Flush Mixed 205 sks owc 5# per sk water
1/4 190 C.F.L. 115. displaced with 123 bbl H2O with 90# psi pressure.
plug landed at 1500' washed out pump lines. rigged down and left
location.

Cent. on #3 1, 6, 21, 63, 65 turbolizer on #3 2, 3, 4, 5, 18, 19, 20
basket on #64 portcollar on top of #64 scratchers on 19, 20, 21
Shamba
Kelly & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
5401 P	1	PUMP CHARGE	2950.00	2950.00
5407	75	MILEAGE	5.00	375.00
1126	205 sks	OWC cement	21.48	4403.40
110A	1000 #	Kel seal	.53	530.00
1137X	48 #	C.F.L. 115	9.95	477.60
1102	240 #	Calcium chloride	.84	201.60
111A	200 #	Sodium Metasilicate	2.36	472.00
5407A	10.7	Ton Mileage delivery	1.58	1268.25
4104	1	5 1/2 cement Basket	276.00	276.00
4105	5	5 1/2 centralizer	58.00	290.00
4136	2	5 1/2 turbolizer	72.00	144.00
4253	1	5 1/2 Packer shoe	1760.00	1760.00
4454	1	5 1/2 Latchdown assembly	303.00	303.00
4285	1	5 1/2 Portcollar	2075.00	2075.00
4314	10	Reciprocating scratcher 5 1/2	78.00	780.00
		Subtotal		16645.40
		Lead 15% discount		2496.81
				14148.59
				729.08
				14948.05

Rev 3737

AUTHORIZATION

TITLE

SALES TAX
ESTIMATED
TOTAL

DATE

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.

CONSOLIDATED
ON Wall Street, U.S.

PO Box 684, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER 28163

LOCATION Oakley KS

FOREMAN Walt Dink

FIELD TICKET & TREATMENT REPORT
CEMENT

Colorado

DATE			CUSTOMER #		WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
8-17-11			5659		APC Tunnel # 1-33		33	17 ^s	24 ^{sw}	Kiowa
CUSTOMER						Brandon 6 N 2 W 1/4 S E. 3	TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS							399	Kelly Gable		
							528-T127	Damon Miller		
							566	Wilas Shaw		
CITY				STATE	ZIP CODE	CASING SIZE & WEIGHT 10.5" - 14"				

JOB TYPE <u>Port Collar</u>	HOLE SIZE <u>7 7/8</u>	E.O. <u> </u>	HOLE DEPTH <u> </u>	CASING SIZE & WEIGHT <u>25 1/2 - 14 3/4</u>
CASING DEPTH <u> </u>	DRILL PIPE <u> </u>	TUBING <u>2 7/8 - 2400'</u>	OTHER <u>PC 2400'</u>	
SLURRY WEIGHT <u>12.5 - 14</u>	SLURRY VOL <u> </u>	WATER gal/sk <u> </u>	CEMENT LEFT in CASING <u> </u>	
		MIX PSI <u> </u>	RATE <u> </u>	

DISPLACEMENT 13.881 DISPLACEMENT PSI MIX PSI RATE
REMARKS: Safety, Working, Rig up in Tunnel # Test Casing to 1500' Hold
released Pressure, open tool mixed 375 sks 59% oil, 8% gel, 14% Fl
sand, Tail in w/ 50 sks com, Displace 13.881 H₂O. shut Tool, Test to 1500'
Hold, run 4 1/2 hrs, washed out clean,

Cement Did Cure

Thank You

Waff-Cr.

[illegible]

Bayln 2737

AUTHORIZATION

TITL

DATE _____

**ESTIMATED
TOTAL**

AUTHORIZATION _____ **FILE #** _____
I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.