

GREAT WESTERN OIL & GAS COMPANY
Well Name: MERSHON 26-33
SWSE, Sect. 26, Twp 6N, Rng 67W
Weld County, CO
CURRENT WELLBORE SCHEMATIC as of June 24, 2011

API: 05-123-23134-00

GL Elev: 4745'
KB Elev: 4757'

Spud: 9/16/2005

Surface Casing :
8-5/8" 24# set @ 414'
Cement w/ 330 sx. Cmt to surface

Tubing Detail:

6/20/2011: 2-3/8" 4.7# J-55 (219) jnts + 18' subs
landed at 7239' KB (= 15' above Codell)

Production Casing :

9/21/2005: 4-1/2" 11.6# set @ 7416'
Cement w/ 250 sx

