

FORM
2

Rev
12/05

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE	ET	OE	ES
----	----	----	----

Document Number:

400184609

PluggingBond SuretyID

20080134

APPLICATION FOR PERMIT TO:

1. ☒ Drill, ☐ Deepen, ☐ Re-enter, ☐ Recomplete and Operate

2. TYPE OF WELL

OIL ☒ GAS ☐ COALBED ☐ OTHER _____
SINGLE ZONE ☒ MULTIPLE ☐ COMMINGLE ☐

Refiling ☐

Sidetrack ☐

3. Name of Operator: PINE RIDGE OIL & GAS LLC

4. COGCC Operator Number: 10276

5. Address: 600 17TH ST STE 800S

City: DENVER State: CO Zip: 80202

6. Contact Name: PAUL GOTTLÖB Phone: (303)226-1316 Fax: (303)226-1301

Email: Paul.Gottlob@cometridgeresources.com

7. Well Name: King Well Number: 12-28

8. Unit Name (if appl): _____ Unit Number: _____

9. Proposed Total Measured Depth: 3551

WELL LOCATION INFORMATION

10. QtrQtr: SWNW Sec: 28 Twp: 19S Rng: 69W Meridian: 6

Latitude: 38.368186 Longitude: -105.122245

Footage at Surface: 2157 feet FNL 997 feet FWL

11. Field Name: FLORENCE-CANON CITY Field Number: 24600

12. Ground Elevation: 5357 13. County: FREMONT

14. GPS Data:

Date of Measurement: 06/23/2011 PDOP Reading: 1.7 Instrument Operator's Name: Chris Pearson

15. If well is ☒ Directional ☐ Horizontal (highly deviated) **submit deviated drilling plan.**

Footage at Top of Prod Zone: 1924 FNL 928 FWL 1042 FNL 592 FWL
Sec: 28 Twp: 19S Rng: 69W Sec: 28 Twp: 19S Rng: 69W

16. Is location in a high density area? (Rule 603b)? ☐ Yes ☒ No

17. Distance to the nearest building, public road, above ground utility or railroad: 185 ft

18. Distance to nearest property line: 157 ft 19. Distance to nearest well permitted/completed in the same formation: 1220 ft

20. LEASE, SPACING AND POOLING INFORMATION

Objective Formation(s)	Formation Code	Spacing Order Number(s)	Unit Acreage Assigned to Well	Unit Configuration (N/2, SE/4, etc.)
Pierre	PRRE			

21. Mineral Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian Lease #: _____

22. Surface Ownership: ☒ Fee ☐ State ☐ Federal ☐ Indian

23. Is the Surface Owner also the Mineral Owner? ☐ Yes ☒ No Surface Surety ID#: 20080135

23a. If 23 is Yes: Is the Surface Owner(s) signature on the lease? ☐ Yes ☐ No

23b. If 23 is No: ☐ Surface Owners Agreement Attached or ☒ \$25,000 Blanket Surface Bond ☐ \$2,000 Surface Bond ☐ \$5,000 Surface Bond

24. Using standard QtrQtr, Sec, Twp, Rng format enter entire mineral lease description upon which this proposed wellsite is located (attach separate sheet/map if you prefer):

See attachment

25. Distance to Nearest Mineral Lease Line: 592

26. Total Acres in Lease: 2583

DRILLING PLANS AND PROCEDURES

27. Is H2S anticipated? ☐ Yes ☒ No If Yes, attach contingency plan.

28. Will salt sections be encountered during drilling? ☐ Yes ☒ No

29. Will salt (>15,000 ppm TDS CL) or oil based muds be used during drilling? ☐ Yes ☒ No

30. If questions 28 or 29 are yes, is this location in a sensitive area (Rule 901.e)? ☐ Yes ☐ No

31. Mud disposal: ☐ Offsite ☒ Onsite

If 28, 29, or 30 are "Yes" a pit permit may be required.

Method: ☐ Land Farming ☐ Land Spreading ☐ Disposal Facility Other: Evaporation and burial

Note: The use of an earthen pit for Recompletion fluids requires a pit permit (Rule 905b). If air/gas drilling, notify local fire officials.

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Btm	Cmt Top
CONDUCTOR	24	16	1/4Wt	0	60	5	60	0
SURF	12+1/4	8+5/8	24	0	660	170	660	0
1ST	7+7/8	5+1/2	15.5	0	3,551			

32. BOP Equipment Type: ☐ Annular Preventer ☒ Double Ram ☒ Rotating Head ☐ None

33. Comments Conductor cement volume is expressed in cubic yards. Production casing will not be cemented.

34. Location ID: 419944

35. Is this application in a Comprehensive Drilling Plan ? ☐ Yes ☐ No

36. Is this application part of submitted Oil and Gas Location Assessment ? ☒ Yes ☐ No

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: _____

Print Name: PAUL GOTTLOB

Title: Sr. Engineering Tech.

Date: 7/19/2011

Email: Paul.Gottlob@

Based on the information provided herein, this Application for Permit-to-Drill complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: David S. Neslin

Director of COGCC Date: 8/31/2011

API NUMBER

05 043 06211 00

Permit Number: _____ Expiration Date: 8/30/2013

CONDITIONS OF APPROVAL, IF ANY:

All representations, stipulations and conditions of approval stated in the Form 2A for this location shall constitute representations, stipulations and conditions of approval for this Form 2 Permit-to-Drill and are enforceable to the same extent as all other representations, stipulations and conditions of approval stated in this Permit-to-Drill.

- 1) Provide 48 hour notice of MIRU to Mike Leonard at 719-647-9715 or e-mail at mike.leonard@state.co.us.
- 2) Set surface casing to at least 660' per Rule 317d, cement to surface.
- 3) Comply with Rule 321. Run and submit directional survey from TD to surface. Ensure that the wellbore complies with setback requirements in commission orders or rules prior to producing the well.
- 4) If well is a dry hole, set 50 sks cement across surface casing shoe, 15 sks cement in top of surface casing, cut off casing 4' below GL, weld on plate, 5 sks cement in rat hole & 5 sks cement in mouse hole.

Attachment Check List

Att Doc Num	Name
1792277	CORRESPONDENCE
2568896	SURFACE CASING CHECK
400184609	FORM 2 SUBMITTED
400186713	LEGAL/LEASE DESCRIPTION
400186717	LEASE MAP
400186719	DEVIATED DRILLING PLAN
400186720	PLAT
400186723	TOPO MAP

Total Attach: 8 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>
Permit	The rig height will be 89'. Email from Paul Gottlob. BY	8/31/2011 12:15:45 PM
Permit	SHL and BHL are within the general outline of the Florence Field and the objective is a fractured shale. BY	8/23/2011 12:43:55 PM
Permit	No answer to #15 and 36. Location ID should be filled out.	7/20/2011 6:57:03 AM

Total: 3 comment(s)

BMP

<u>Type</u>	<u>Comment</u>

Total: 0 comment(s)