

FORM
5A
Rev
02/08

State of Colorado
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:
400201951

COMPLETED INTERVAL REPORT

The completed interval Report, Form 5A, shall be submitted within thirty (30) days of completing a formation (successful or not), when a formation is temporarily abandoned or permanently abandoned, for a recompletion, reperforation or restimulation, or when a formation is commingled. Fill out a section for each formation. Attach as many pages as required to fully describe the work. List in order of completion.

1. OGCC Operator Number: 100322
2. Name of Operator: NOBLE ENERGY INC
3. Address: 1625 BROADWAY STE 2200
City: DENVER State: CO Zip: 80202
4. Contact Name: Justin Garrett
Phone: (303) 228-4449
Fax: (303) 228-4286

5. API Number 05-123-12872-00
6. County: WELD
7. Well Name: FRANK
Well Number: 6
8. Location: QtrQtr: SENW Section: 7 Township: 4N Range: 63W Meridian: 6
9. Field Name: WATTENBERG Field Code: 90750

Completed Interval

FORMATION: NIOBRARA-CODELL Status: PRODUCING

Treatment Date: 04/18/2011 Date of First Production this formation: 11/16/2005

Perforations Top: 6390 Bottom: 6655 No. Holes: 248 Hole size:

Provide a brief summary of the formation treatment: Open Hole:

Codell trfrac
Codell & Niobrara are commingled
Niobrara 6390'-6478', 192 holes
Nothing new happened in Niobrara during Codell trfrac
Codell 6654'-6665', 56 holes
Frac'd Codell w/123844 gals Vistar and Slick Water with 243000 lbs Ottawa sand

This formation is commingled with another formation: Yes No

Test Information:

Date: 06/03/2011 Hours: 24 Bbls oil: 1 Mcf Gas: 45 Bbls H2O: 1

Calculated 24 hour rate: Bbls oil: 1 Mcf Gas: 45 Bbls H2O: 1 GOR: 45000

Test Method: Flowing Casing PSI: 280 Tubing PSI: 275 Choke Size: 13/64

Gas Disposition: SOLD Gas Type: WET BTU Gas: 1357 API Gravity Oil: 57

Tubing Size: 2 + 3/8 Tubing Setting Depth: 6631 Tbg setting date: 04/21/2011 Packer Depth:

Reason for Non-Production:

Date formation Abandoned: Squeeze: Yes No If yes, number of sacks cmt

Bridge Plug Depth: Sacks cement on top:

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: Print Name: Justin Garrett

Title: Regulatory Specialist Date: JDGarrett@nobleenergyinc.com

Email
:

Based on the information provided herein, this Completed Interval Report (Form 5A) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: _____ Director of COGCC Date: _____

Attachment Check List

Att Doc Num	Name

Total Attach: 0 Files

General Comments

<u>User Group</u>	<u>Comment</u>	<u>Comment Date</u>

Total: 0 comment(s)