



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199707

Date	6-14-11	Well Owner	Kerr McGee	Well No.	22-14	Lease	SWEETGRASS
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (XTREME-12)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Ft.	1203		
Surface	8 7/8" CSG-24 #	Bottom of Surface		Ft.	1194		
Plug		Plug Landed @	1150	Ft.	Time On	1515	
Production		Pipe Landed @	1194	Ft.	Plug Down	1745	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat TYPE III	750	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Flo-Cete 1/4 # Per Sack				
Mileage Charge	222	Miles		
Fuel Surcharge	222	MILES		
Additional Cement	40	SKS		
Mixing Rate	4 BPM	Pre-Flush	1632	1640
Disp. Rate	5 BPM	Mixing	1640	1727
Slurry Vol.	1.32 ³ Cu. Ft./Sk	Change Valves	1727	1730
Slurry Wt.	14.8 - 15.0 PPG	Displacement	1730	1745
Water/Cement	6.25 Gal/SK			
Water Temp.	68°F			
Total Slurry Vol.	185.7	BBLS Cement		
Landed Plug @	950	PSI/Final Lift @	450	PSI
Pre-Flush W/	30	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	73.1	BBLS H ₂ O	State	CO 2.9%
Circulate	5	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1202		Pump Truck		74			
1216/1207		Bulk Truck		74/74			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By JOE, JOSH, EVAN, ERNIE

Received By

Customer or His Agent