



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199608

Date <u>5/14/11</u>	Well Owner <u>Kerr McGee</u>	Well No. <u>25-14</u>	Lease <u>Sweetgrass</u>
County <u>Weld</u>	State <u>Colorado</u>		
Charge to <u>Kerr McGee Oil & Gas Onshore, LP</u>			
Address <u>1999 Broadway, Suite 3700 (Xtreme #12)</u>			
City, State Zip <u>Denver, Colorado 80202</u>			
Type of Job	Depth	FL <u>1212</u>	
<u>Surface</u> <u>8 5/8" C50-24"</u>	Bottom of Surface	FL <u>1202</u>	
Plug	Plug Landed @ <u>1158</u>	Fl. Time On <u>0730</u>	
Production	Pipe Landed @ <u>1202</u>	Fl. Plug Down <u>1030</u>	

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat <u>Type III</u>	760	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Fio-Cete 1/4 # Per Sack <u>2046302 DRI</u>				
Mileage Charge	216	Miles		
Fuel Surcharge <u>80012090-</u>	216	Miles		
Additional Cement		SKS		
Mixing Rate 4 BPM	Pre-Flush	0933	0939	
Disp. Rate 5 BPM	Mixing	0939-	1012	
Slurry Vol. 1.32 ³ Cu.Fl./Sk	Change Valves	1012-	1015	
Slurry Wt. 14.8 - 15.0 PPG	Displacement	1015-	1030	
Water/Cement 6.25 Gal/SK				
Water Temp. <u>56°F</u>				
Total Slurry Vol. <u>178.5</u>	BBLS Cement			
Landed Plug @ <u>900</u>	PSI/Final Lift @ <u>400</u>	PSI		
Pre-Flush W/ <u>30</u>	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ <u>73.5</u>	BBLS H ₂ O	State <u>CO 2.9%</u>	Tax	
Circulate <u>6</u>	BBLS Cement		Total	

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
<u>1208</u>		Pump Truck		<u>72</u>			
<u>1214/1217</u>		Bulk Truck		<u>72/72</u>			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Dallas, Justin Demetrio

Received By J. Joel

Customer or His Agent