



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199737

Date	7/4/11	Well Owner	Kerr McGee	Well No.	22-36	Lease	CARMA
County	Weld	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (Xtreme #11)						
City, State Zip	Denver, Colorado 80202						
Type of Job				Depth	FL 858		
Surface	8 5/8" CSG-24"			Bottom of Surface	FL 843		
Plug				Plug Landed @	799	FL	Time On 0315
Production				Pipe Landed @	843	FL	Plug Down 0745

Description	Qty	Meas.	Unit Price	Amount
Set Up/Charge	1			
Cement Neat ✓ Type III 100% Express	530	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel % Fio-Cete 1/4 # Per Sack 2039910 DRL				
Mileage Charge 800/2090	156	Miles		
Fuel Surcharge	156	Miles		
Additional Cement	20	SKS		
Mixing Rate 4 BPM	Pre-Flush			
Disp. Rate 5 BPM	Mixing	0703 0709		
Slurry Vol. 1.32 Cu. Ft./Sk	Change Valves	0709-0732		
Slurry Wt. 14.8 - 15.0 PPG	Displacement	0732-0735		
Water/Cement 6.25 Gal/SK		0735-0745		
Water Temp 60°F				
Total Slurry Vol. 129	BBLS Cement			
Landed Plug @ 450	PSI/Final Lift @ 300	PSI		
Pre-Flush W/ 30	BBLS H ₂ O	Tax Reference Code	Sub Total	
Displace W/ 51	BBLS H ₂ O	State CO 2.9%	Tax	
Circulate 0	BBLS Cement	Total		

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1208		Pump Truck		26			
1210/1218		Bulk Truck		26/26			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Justin Dallas & Demetrio

Received By

Tom Bowler

Customer or His Agent