

FD. 2" ALUM. CAP  
LS #9185 (1977)

FD. 1/2" IRON BAR  
LS #6728 (1990)

FD. REBAR

FD. 2" ALUM. CAP  
LS#9185 (1977)



23

FD. 2" ALUM. CAP  
LS #5836

NO MONUMENT  
FOUND OR SET

NO MONUMENT  
FOUND OR SET

DRILLING  
WINDOW

N01°28'05"W 3966.8 ± (MEAS.)

90°

WITT GU 34-23 #2  
BOTTOM HOLE LOCATION  
2503.3' FWL  
1224.3' FSL

LAT. 37.17276 N  
LONG. 107.68708 W  
ELEV. UNGRADED  
GROUND = 6678.617'  
N = 1191739.843  
E = 2362797.566

2503.3 ± FWL (MEAS.)

660'

660'

90°

1224.3 ± FSL (MEAS.)

660'

660'

FD. 2" ALUM. CAP  
LS #9185 (1977)

BASIS OF BEARING  
N88°22'40"W 2649.5 ± (MEAS.)


FD. 3/4" ALUM. CAP  
LS #9187

N88°21'20"W 2656.3 ± (MEAS.)

FD. 3/4" ALUM. CAP  
LS #9187 (1992)

OPERATOR: BP AMERICA PRODUCTION COMPANY  
LEASE: WITT GU 34-23 #2  
SECTION 23 TOWNSHIP 34 NORTH RANGE 8 WEST N.M.P.M.  
COUNTY: LA PLATA COUNTY, COLORADO

SURFACE LOCATION OF WELL: 1224.3 FEET FROM THE SOUTH LINE, AND  
2503.3 FEET FROM THE WEST LINE  
BOTTOM HOLE LOCATION: 1224.3 FEET FROM THE SOUTH LINE, AND  
2503.3 FEET FROM THE WEST LINE  
GROUND LEVEL ELEVATION: 6678.617'



LEGEND:  
● = PROPOSED WELL HEAD  
○ = BOTTOM HOLE LOCATION  
▲ = SECTION CORNERS LOCATED  
△ = SECTION CORNERS NOT FOUND OR SET  
THIS SURVEY (CALCULATED LOCATION).  
S.U.I.T. = SOUTHERN UTE INDIAN TRIBE  
BLM = BUREAU OF LAND MANAGEMENT

**SURVEYOR'S STATEMENT:**

I, GARY D. GABLE, A LICENSED PROFESSIONAL LAND SURVEYOR IN THE STATE OF COLORADO, DO HEREBY STATE THAT THE WELL LOCATION SHOWN ON THIS PLAT WAS PLOTTED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY RESPONSIBLE CHARGE, AND THAT THIS PLAT IS NOT A LAND SURVEY PLAT OR AN IMPROVEMENT SURVEY PLAT, AND THAT IT IS NOT TO BE RELIED UPON FOR THE ESTABLISHMENT OF FENCE, BUILDING, OR OTHER FUTURE IMPROVEMENT LINES. SAID SURVEY IS ACCURATE TO THE BEST OF MY KNOWLEDGE AND BELIEF.

GARY D. GABLE  
P.L.S. #24662

NOTE: THIS EXHIBIT IS INTENDED ONLY TO DEPICT THE PROPOSED WELL LOCATION AND DOES NOT REPRESENT A MONUMENTED BOUNDARY SURVEY.

- 1) ALL MEASUREMENTS SHOWN HEREON ARE GROUND MEASUREMENTS
- 2) BASIS OF BEARING: SPC, C-SO, NAD83 ALONG SOUTH LINE OF THE SW1/4 OF SAID SECTION 23 BEARS: N88°22'40"W
- 3) DATE FIELD SURVEY: 4/27/11
- 4) ELEVATION DETERMINED FROM NAVD 1988 DATUM, AND DETERMINED USING GPS OBSERVATIONS.
- 5) THERE ARE NO IMPROVEMENTS WITHIN 200 FEET OF THE LOCATION.
- 6) AGRICULTURAL SURFACE USE.
- 7) BOTTOM HOLE LOCATION PROVIDED BY BP
- 8) INSTRUMENT OPERATOR: BILL MITCHELL
- 9) PDP VALUE: 2.2

Drawing: WITT\_GU34-23\_2-APPD.DWG Plotted by: DALLAS\_KNOLL Date: 08/17/2011 01:30:56 PM R:\Project Files\BPA\BP 80 Acres Infill\Witt GU 34-23 #2 #4\Permitting Drawings\

	PROJ. NO.	FILE NO.	WITT_GU34-23_2-APD	WITT GU 34-23 #2 WELL LOCATION PLAT	REV E
	8572				
	DRAWN BY	DATE	CLIENT	BP AMERICA PROD. CO. - DURANGO, CO	
	DK	8/17/11	PC		