

FORM  
5Rev  
02/08State of Colorado  
Oil and Gas Conservation Commission

1120 Lincoln Street, Suite 801, Denver, Colorado 80205 Phone: (303) 894-2100 Fax: (303) 894-2109



DE ET OE ES

Document Number:

400204066

## DRILLING COMPLETION REPORT

This form is to be submitted within 30 days of the setting of production casing, the plugging of a dry hole, the deepening or sidetracking of a well, or any time the wellbore configuration is changed. If the well is deepened or sidetracked a new Form 5 is required. If an attempt has been made to complete/produce a well, then the operator shall submit Form 5A (Completed Interval Report.) If the well has been plugged, a form 6 (Well Abandonment Report) is required.

Completion Type ☒ Final completion ☐ Preliminary completion

1. OGCC Operator Number: 47120

2. Name of Operator: KERR-MCGEE OIL &amp; GAS ONSHORE LP

3. Address: P O BOX 173779

City: DENVER State: CO Zip: 80217-

4. Contact Name: Cindy Vue

Phone: (720) 929-6832

Fax: (720) 929-7832

5. API Number 05-123-33129-00

6. County: WELD

7. Well Name: NICHOLS

Well Number: 24-8

8. Location: QtrQtr: NWNE Section: 8 Township: 2N Range: 65W Meridian: 6

Footage at surface: Distance: 513 feet Direction: FNL Distance: 2630 feet Direction: FEL

As Drilled Latitude: 40.159118 As Drilled Longitude: -104.687690

GPS Data:

Data of Measurement: 07/15/2011 PDOP Reading: 2.7 GPS Instrument Operator's Name: Renee Doiron

\*\* If directional footage

at Top of Prod. Zone Distance: 2575 feet Direction: FNL Distance: 1446 feet Direction: FEL

Sec: 8 Twp: 2N Rng: 65W

at Bottom Hole Distance: 2582 feet Direction: FNL Distance: 1438 feet Direction: FEL

Sec: 8 Twp: 2N Rng: 65W

9. Field Name: WATTENBERG

10. Field Number: 90750

11. Federal, Indian or State Lease Number:

12. Spud Date: (when the 1st bit hit the dirt) 06/24/2011 13. Date TD: 06/27/2011 14. Date Casing Set or D&amp;A: 06/28/2011

15. Well Classification:

☐ Dry ☒ Oil ☐ Gas/Coalbed ☐ Disposal ☐ Stratigraphic ☐ Enhanced Recovery ☐ Storage ☐ Observation

16. Total Depth MD 8397 TVD 7826 17 Plug Back Total Depth MD 8334 TVD 7763

18. Elevations GR 4877 KB 4891

One paper copy of all electric and mud logs must be submitted, along with one digital LAS copy as available.

19. List Electric Logs Run:

OPEN HOLE LOGS BRIDGED OUT @ 2349'.  
CBL

20. Casing, Liner and Cement:

## CASING

Casing Type	Size of Hole	Size of Casing	Wt/Ft	Csg/Liner Top	Setting Depth	Sacks Cmt	Cmt Top	Cmt Bot	Status
SURF	12+1/4	8+5/8	24#	0	824	530	14	824	CALC
1ST	7+7/8	4+1/2	11.6#	0	8,352	233	6,698	8,352	CBL

## ADDITIONAL CEMENT

Cement work date: 06/28/2011

Details of work:

Method used	String	Cementing tool setting/pref depth	Cement volume	Cement top	Cement bottom
DV TOOL	1ST	5,737	715	1,270	5,770

21. Formation log intervals and test zones:

### FORMATION LOG INTERVALS AND TEST ZONES

FORMATION NAME	Measured Depth		Check if applies		COMMENTS (All DST and Core Analyses must be submitted to COGCC)
	Top	Bottom	DST	Cored	
NIOBRARA	7,554		<input type="checkbox"/>	<input type="checkbox"/>	
CODELL	7,784		<input type="checkbox"/>	<input type="checkbox"/>	
J SAND	8,240		<input type="checkbox"/>	<input type="checkbox"/>	

Comment:

I hereby certify all statements made in this form are, to the best of my knowledge, true, correct, and complete.

Signed: \_\_\_\_\_ Print Name: Cindy Vue

Title: Regulatory Analyst II Date: \_\_\_\_\_ Email: Cindy.Vue@anadarko.com

Based on the information provided herein, this Drilling Completion Report (Form 5) complies with COGCC Rules and applicable orders and is hereby approved.

COGCC Approved: \_\_\_\_\_ Director of COGCC Date: \_\_\_\_\_

### Attachment Check List

Att Doc Num	Name
400204067	DIRECTIONAL SURVEY
400204068	CEMENT JOB SUMMARY

Total Attach: 2 Files

### General Comments

User Group	Comment	Comment Date

Total: 0 comment(s)