



CEMENTER'S WELL SERVICE, INC.

P.O. BOX 336220 • GREELEY, CO 80633 • (970) 353-7299 • FAX (970) 353-7712

OUR INVOICE

199686

Date	6/24/11	Well Owner	Kerr McGee	Well No.	24-8	Lease	Nichols
County	WELD	State	Colorado				
Charge to	Kerr McGee Oil & Gas Onshore, LP						
Address	1999 Broadway, Suite 3700 (PATTERSON# 189)						
City, State Zip	Denver, Colorado 80202						
Type of Job		Depth		Fl.	848		
Surface	8 5/8 csg #24	Bottom of Surface		Fl.	841		
Plug		Plug Landed @	797	Fl.		Time On	1800
Production		Pipe Landed @	841	Fl.		Plug Down	2015

Description	Qty.	Meas.	Unit Price	Amount
Set Up Charge	1			
Cement Neat Type III	530	SKS		
Poz. Mix				
Calcium Chloride	2.5	%		
Gel. % Flo-Crete 1/4 # Per Sack	800/2090			
Mileage Charge	126	Miles		
Fuel Surcharge	126	miles		
Additional Cement		SKS		
Mixing Rate	4 BPM	Pre-Flush	1936	1540
Disp. Rate	5 BPM	Mixing	1940	2002
Slurry Vol.	1.32 ³ Cu. Ft./Sk	Change Valves	2062	2005
Slurry Wt.	14.8 - 15.0 PPG	Displacement	2005	2015
Water/Cement	6.25 Gal/SK			
Water Temp.	65°F			
Total Slurry Vol.	124.5	BBLS Cement		
Landed Plug @	250	PSI/Final Lift @	140	PSI
Pre-Flush W/	20	BBLS H ₂ O	Tax Reference Code	Sub Total
Displace W/	50.5	BBLS H ₂ O	State CO 2.9%	Tax
Circulate	6	BBLS Cement		Total

Truck No.	Code	State Mileage	Nebraska	Colorado	Wyoming	Other	Total Mileage
1201		Pump Truck		42			
1216/1217		Bulk Truck		42/42			

We do not assume any responsibility for any damage or conditions resulting from our services. All pricing is subject to review and revision.

Delivered By Jim/Adam/Steve/Cris/Kenny

Received By Danny Na
Customer or His Agent